PERMANENT FASEMENT PROPERTY LINE HORIZONTAL CONTROL POINT BENCHMARK SURVEY MARKER SOIL BORING SANITARY SEWER AND MANHOLE FORCE MAIN AND LIFT STATION SANITARY SEWER SERVICE & CLEANOUT WATER MAIN, HYDRANT, VALVE AND MANHOLE WATER SERVICE AND CURB STOP BOX STORM SEWER, MANHOLE AND CATCH BASIN CULVERT AND APRON ENDWALL GAS MAIN, VALVE, VENT AND METER BURIED FIBER OPTIC CABLE AND MANHOLE BURIED PHONE CABLE, PEDESTAL AND MANHOLE BURIED TV CABLE, PEDESTAL AND MANHOLE BURIED ELECTRIC CABLE, PEDESTAL, MANHOLE, TRANSFORMER AND METER OVERHEAD WIRE, POLE AND GUY WIRE LIGHT POLE TRAFFIC SIGNAL STREET NAME SIGN SIGN (NON STREET NAME) RAILROAD TRACKS DECIDUOUS AND CONIFEROUS TREE O AXX BUSH / SHRUB AND STUMP EDGE OF WOODED AREA FENCE (UNIDENTIFIED) BARBED WIRE FENCE CHAIN LINK FENCE **ELECTRIC WIRE FENCE** WOOD FENCE WOVEN WIRE FENCE PLATE BEAM GUARDRAIL CABLE GUARDRAIL POST / BOLLARD **PROPOSED** —— STREET CENTERLINE CONSTRUCTION LIMITS SANITARY SEWER, BULKHEAD AND MANHOLE SANITARY SERVICE AND CLEANOUT WATER MAIN, TEE, HYDRANT, BULKHEAD AND VALVE WATER VALVE MANHOLE, REDUCER, BEND AND CROSS WATER SERVICE AND CURB STOP BOX STORM SEWER MANHOLE AND CATCH BASIN CULVERT AND APRON ENDWALL -<---- DRAIN TILE -<-- DITCH / SWALE RIPRAP STREET NAME SIGN SIGN (NON STREET NAME) 90% PLANS

CITY OF NORTHFIELD, **MINNESOTA**

CONSTRUCTION PLANS FOR

GRADING, TRAIL PAVING, STORM **SEWER & RETAINING WALL**

TRUNK HIGHWAY 246 TRAIL

CITY PROJECT NO. STRT2024-A79 SP 6614-33




THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS UTILITY QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-22 ENTITLED STANDARD GUIDELINES FOR INVESTIGATING AND DOCUMENTING EXISTING UTILITIES.

THE CONTRACTOR SHALL CALL THE ONE CALL SYSTEM AT 811 BEFORE COMMENCING EXCAVATION



PROJECT LOCATION



RANGE: 19 SECTION: 6



Know what's below. Call before you dig

THE 2020 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" SHALL GOVERN EXCEPT
AS MODIFIED BY THE SPECIFICATIONS FOR THIS PROJECT.

LL TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE LATEST EDITION OF THE

INDEX

DESCRIPTION

TITLE SHEET STATEMENT OF ESTIMATED QUANTITIES ALIGNMENT PLAN

TYPICAL SECTIONS CONSTRUCTION PHASING CITY DETAILS

MNDOT STANDARD PLANS REMOVAL PLAN TRAIL & STORM SEWER PLAN 20-21 INTERSECTION DETAIL

RETAINING WALL PLAN & DETAILS 23-24 25 CURB AND GUTTER PLAN

29 30 **EROSION CONTROL & RESTORATION PLAN**

LANDSCAPING AND PLANTINGS PLAN 31-33 TRAFFIC CONTROL NOTES AND PLAN SIGNING AND STRIPING PLAN & DETAILS

THIS PLAN CONTAINS 42 SHEETS.

DESIGN DESIGNATION

STOPPING SIGHT DISTANCE BASED ON:

STREET NAME SP 6614-33

GROSS LENGTH NET LENGTH DESIGN SPEED

SHEET NO.

10-18

1200 FEET 0.227 MILES 1200 FEET 0.227 MILES

2' HEIGHT OF OBJECT

DATE

PROJECT NO

176070

of 42

LOCAL AGENCY SIGNATURE:

APPROVED: CITY ENGINEER OF NORTHFIELD DATE

STATE APPROVALS:

DISTRICT STATE AID ENGINEER: REVIEWED FOR

APPROVED FOR STATE AID FUNDING

NORTHFIELD. MINNESOTA



HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFFESIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SP 6614-33

PLACEHOLDER FOR STATEMENT OF ESTIMATED QUANTITIES

ACB



GENERAL GRADING AND DRAINAGE NOTES:

- 1. WORKING HOURS SHALL COMPLY WITH THE CITY OF NORTHFIELD ORDINANCE OF 7 A.M. TO 7 P.M., MONDAY THROUGH FRIDAY WORKING ON SATURDAYS WILL BE PERMITTED WITH PERMISSION FROM THE ENGINEER. CONTRACTOR MUST PROVIDE 48 HOUR NOTICE TO THE ENGINEER OF THEIR INTENT TO WORK ON SATURDAY. UNLESS WRITTEN AUTHORIZATION IS GRANTED BY THE CITY OF NORTHFIELD, THE START-UP OF MACHINERY SHALL NOT OCCUR OUTSIDE THIS TIME FRAME. NO WORK WILL BE ALLOWED ON SUNDAYS OR HOLIDAYS.
- 2. (P) DENOTES A PLAN QUANTITY ITEM.
- 3. THE CONTRACTOR SHALL CALL THE GOPHER STATE ONE CALL SYSTEM AT 811 BEFORE COMMENCING EXCAVATION.
- 4. THE LOCATION OF EXISTING UTILITIES SHOWN ARE APPROXIMATE AND MAY NOT BE COMPLETE. THE CONTRACTOR SHALL FIELD VERIFY THE LOCATION AND ELEVATION OF EXISTING UTILITIES AND TOPOGRAPHICAL FEATURES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER OF ANY DISCREPANCIES OR VARIATIONS FROM PLAN. THE CONTRACTOR SHALL GIVE 48 HOURS NOTICE TO THE OWNERS OF ALL KNOWN UTILITIES BEFORE STARTING ANY OPERATIONS AFFECTING THOSE PROPERTIES. OR BEGINNING EXCAVATION IN THE VICINITY OF THOSE PROPERTIES.
- 5. SOME UTILITY COMPANIES MAY RELOCATE THEIR FACILITIES CONCURRENTLY WITH THE CONSTRUCTION OPERATIONS UNDER THIS CONTRACT. CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANIES AND SCHEDULE RELOCATION.
- 6. CONTRACTOR TO CONTACT UTILITY COMPANIES AND COORDINATE RELOCATION OF UTILITIES AS
- 7. BACKFILLING OF CURBS WITH ON-SITE MATERIAL IS INCIDENTAL.
- 8. ANY USE OF SHORING, OR OTHER METHODS OR MEANS OF CONSTRUCTION NECESSARY TO COMPLETE. CONSTRUCTION WITHIN THE CONSTRUCTION LIMITS OR SLOPE EASEMENTS SHOWN WILL BE CONSIDERED INCIDENTAL, AND NO DIRECT COMPENSATION WILL BE MADE THEREOF
- 9. ALL USES OF THE WORD "INCIDENTAL" IN THESE CONSTRUCTION DOCUMENTS SHALL BE CONSTRUED TO MEAN INCIDENTAL WORK FOR WHICH NO DIRECT COMPENSATION WILL BE MADE.
- 10. TRAFFIC CONTROL SHALL COMPLY WITH MINNESOTA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- 11. THE CONTRACTOR SHALL COORDINATE UTILITY AND TRAIL WORK WITHIN THE PROJECT LIMITS. CONTRACTOR SHALL PROVIDE ACCESS TO ALL PROPERTIES UNLESS ALTERNATE PROVISIONS ARE MADE WITH THE PROPERTY OWNER.
- 12. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DISPOSE OF DEBRIS OFF-SITE THAT EXISTS WITHIN THE CONSTRUCTION AREAS
- 13. NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.
- 14. PROTECT ALL FACILITIES (INCLUDING PRIVATE UTILITIES) NOT DESIGNATED FOR REMOVAL.
- 15. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS LINTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION
- 16. SAWCUT BITUMINOUS AND CONCRETE AS DIRECTED BY THE ENGINEER PRIOR TO REMOVAL. THE CONTRACTOR SHALL SAWCUT PAVEMENT, CURB AND SIDEWALK AS INDICATED ON THE PLANS TO SEPARATE THE EXISTING MATERIAL TO BE REMOVED BY MEANS OF AN APPROVED SAW. SUITABLE GUIDELINES OR DEVICES SHALL BE USED TO ASSURE CUTTING A NEAT, STRAIGHT LINE AS SHOWN ON THE PLANS. CARE SHALL BE TAKEN BY THE CONTRACTOR SO AS NOT TO DAMAGE THE REMAINING MATERIALS DIRECTLY ADJACENT TO THE MATERIALS TO BE REMOVED. ANY DAMAGE TO THE EXISTING MATERIAL RESULTING FROM THE MATERIAL REMOVAL OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- 17. CONSTRUCT ALL RADII AS PER PLANS. ALL RADII SHOWN ARE TO FACE OF CURB UNLESS OTHERWISE NOTED. ALL ELEVATIONS SHOWN ARE AT FLOWLINE UNLESS OTHERWISE NOTED.
- 18. COMPACTION OF TRAIL AGGREGATE BASE SHALL BE ACCOMPLISHED BY THE "DYNAMIC CONE PENETRATION (DCP) METHOD"

GENERAL EROSION CONTROL NOTES:

- 1. ALL PERMITEES, CONTRACTORS, AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PLAN AND THE STATE OF MINNESOTA NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES PHASE II) PERMIT AND BECOME FAMILIAR WITH THEIR CONTENTS AND IS RESPONSIBLE TO COMPLY WITH ALL REQUIREMENTS STATED WITHIN.
- 2. THE BMPS' SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS FOR THE ANTICIPATED SITE CONDITIONS. AS CONSTRUCTION PROGRESSES, THE PERMITEE/ CONTRACTOR SHALL PROVIDE ADDITIONAL BMP'S TO MEET APPLICABLE REQUIREMENTS.
- 3. ALL WORK AND MATERIALS SHALL BE CONSTRUCTED ACCORDING TO THE APPROVED PLANS AND SWPPP. ANY DEVIATION FROM THE APPROVED PLANS SHALL REQUIRE WRITTEN APPROVAL FROM THE OWNER.
- 4. CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL EROSION CONTROL MEASURES AS SHOWN ON THESE PLANS AND SPECIFICATION AND SHALL IMPLEMENT ANY ADDITIONAL FROSION CONTROL MEASURES. NECESSARY, OR AS DIRECTED BY ENGINEER, IN ORDER TO PROTECT ADJACENT PROPERTY.

PROJECT CONTROL NOTES:

- 1. ALL COORDINATES ARE RICE COUNTY COORDINATE SYSTEM.
- 2. HORIZONTAL COORDINATES ARE BASED ON GEODETIC POSITION NAD 83 (1986).
- 3. VERTICAL ELEVATIONS ARE BASED ON NAVD (1988).

SUITABLE MATERIALS

SUITABLE MATERIALS SHALL BE ALL GRANULAR SOILS ENCOUNTERED ON THE PROJECT NOT DEFINED AS BEING UNSUITABLE BY THE ENGINEER.

UNSUITABLE MATERIALS

UNSUITABLE MATERIALS ARE ALL MATERIALS DETERMINED BY THE ENGINEER AS BEING UNSUITABLE FOR GRANULAR BORROW OR STRUCTURAL BACKFILL FOR TRAIL OR ROAD CONSTRUCTION

PROVIDE FOR THE REMOVAL & DISPOSAL, OUTSIDE THE CONSTRUCTION ZONE, OF ANY INPLACE SURFACING OR OTHER STRUCTURES THAT WOULD INTERFERE WITH CONSTRUCTION. ALL SUCH MATERIALS SHALL BECOME THE PROPERTY OF THE CONTRACTOR & SHALL EITHER BE RECYCLED TO THE EXTENT ALLOWED OR DISPOSED OF OFFSITE IN ACCORDANCE WITH SPECIFICATION 2104.3D. PROVIDE FOR SAWCUTTING AS DEEMED NECESSARY BY THE ENGINEER

EXCESS GRADING MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR AND IMMEDIATELY HAULED OFFSITE FOR DISPOSAL

TOPSOIL STRIPPING WILL BE CONSIDERED "COMMON EXCAVATION".

IN FILL SECTIONS. TOPSOIL AND OTHER UNSUITABLE MATERIALS SHALL BE ELIMINATED FROM THE 'GRADING GRADE" BENEATH THE TRAIL

THE FOLLOWING STANDARD PLATES APPROVED BY THE DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION SHALL APPLY ON THIS PROJECT

	STANDARD PLATES		
7038A	DETECTABLE WARNING SURFACE TRUNCATED DOMES		
3000L	REINFORCED CONCRETE PIPE		
3006G	GASKET JOINT FOR RC PIPE		
3007E	SHEAR REINFORCEMENT FOR PRECAST DRAINAGE STRUCTURES		
3100G	CONCRETE APRON FOR REINFORCED CONCRETE PIPE		
3113D	RIPRAP AT RCP OUTLETS		
4101D	RING CASTING FOR MANHOLE OR CATCH BASIN		
4108F	ADJUSTING RINGS FOR CATCH BASINS AND MANHOLES		
7100H	CONCRETE CURB AND GUTTER (DESIGN B AND DESIGN V)		
8000J	CHANNELIZERS		

BASIS OF ESTIMATED QUANTITIES			
WEARING COURSE MIXTURE 113#/SQ YD/INCH			
SEED MIX 35-241	36.5#/ACRE		
SEED MIX 25-131 220#/ACRE			

Date

Rev.#

SEH Project

rawn By

176070


ACB

ACB

Rev.#

Revision Issue Description







ect 176070 Rev.# Revision Issue Date Rev.# Revision Issue


ACB
By ACB
Graph WB

Revision Issue Description Date Rev.# Revision Issue
Description Date Rev.# Description Issue
Description Date Rev.# Description Issue
Description I









PHASE 1: STA 7+50 TO STA 12+95 PHASE 2: STA 0+00 TO STA 7+50

PHASE 1:

- 1. CLOSE SHOULDER AND SHIFT TRAFFIC USING MINNESOTA TEMPORARY TRAFFIC CONTROL FIELD MANUAL LAYOUT 29.
- 2. REMOVE PAVEMENT AND CURB AND GUTTER.
- 3. INSTALL RETAINING WALL.
- 4. COMPLETE STORM SEWER, DRAIN TILE, GRADING, CLASS 5, CURB AND GUTTER, AND BITUMINOUS PAVING.

PHASE 2:

- 1. CLOSE SHOULDER USING MINNESOTA TEMPORARY TRAFFIC **CONTROL FIELD MANUAL LAYOUT 8.**
- 2. COMPLETE STORM SEWER, GRADING, CLASS 5, AND BITUMINOUS
- COMPLETE PERMANENT RESTORATION, SEEDING, AND RAIN GARDEN PLANTINGS.

- 1. IMPACTS TO TRAVEL LANES WILL NOT BE PERMITTED AFTER AUGUST 23, 2024. ONLY SHOULDER CLOSURES WILL BE PERMITTED AFTER THIS DATE.
- 2. WORK IN PHASES 1 AND 2 MAY BE COMPLETED CONCURRENTLY.


TH 246 TRAIL


Rev.# Date Rev.# ACB ACB

WILLIAM BAUER, PE DATE XX-XX-XX


TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

CONSTRUCTION **PHASING**





WILLIAM BAUER, PE



Save: 3/18/2024 6:01 PM nbonanno Plot: 4/26/2024 12:00 PM X:

ACB


ACB

么 SEH 90% PLANS

TRUNK HIGHWAY 246 TRAIL
NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS

10



176070 ACB ACB

Date

Rev.#

Revision Issue Description

Rev.#

Revision Issue Description

90% PLANS

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

(T.H.

STATE PROJ. NO.


THOMAS STYRBICKI STATE DESIGN ENGINEER

MNDOT STANDARD PLANS

0F

SHEET NO.

SHEETS



SEH Project

ACB


ACB

90% PLANS

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS

12




ACB

90% PLANS

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS



ACB

ACB


90% PLANS


TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA


MNDOT STANDARD PLANS

of 42

SP 6614-33







2" MIN. SECTION VIEW A-A

THICKENED SECTION THROUGH CURB RAMP FLARES

CURB AND GUTTER


PROPOSED PAR CURB

CURB RAMP REINFORCEMENT DETAILS 24

LANDING

(3) DRILL AND GROUT 2 - NO. 4 X 12" LONG (6" EMBEDDED) REINFORCEMENT BARS (EPOXY COATED). REINFORCEMENT REQUIRED FOR ALL CONSTRUCTION JOINTS. BARS TO BE PAID BY EACH.

AND GUTTER



TYPICAL SIDEWALK SECTION WITHIN INTERSECTION CORNER

CURB AND GUTTER 3

REINFORCEMENT

LANDING

XISTING CURB AND GUTTER

' MIN.

SAWCUT

36" MAX.

36" MAX.

SAWCUT

3" MIN

12"

SEPARATE LANDING 12 POUR REINFORCEMENT

36" MA

CURB LINE REINFORCEMENT (4) PLACEMENT ON BITUMINOUS ROADWAYS

PEDESTRIAN RAMP PEDESTRIAN RAMP UP TO 2.0% CHANGE 2.0% MAX. OR U TO 4% CHANGE UP TO 2.0% CHANGE UP TO 2.0% CHANGE 2.0% MAX. OR UP TO 4% CHANGE

FLOW LINE PROFILE "TABLE" - TWIN PERPENDICULARS

PEDESTRIAN RAMP UP TO 2.0% CHANGE UP TO 2.0% CHANGE

FLOW LINE PROFILE "TABLE" - FAN



FLOW LINE PROFILE RAISE - TWIN PERPENDICULARS

PEDESTRIAN RAMP 1.0% MIN. 5.0% MAX. 1.0% MIN. 1.5% PREFERRED 1.0% MIN. 5.0% MAX.

FLOW LINE PROFILE RAISE - FAN

GENERAL NOTES:

"TABLING" OF CROSSWALKS MEANS MAINTAINING LESS THAN 2% CROSS SLOPE WITHIN A CROSSWALK, IS REQUIRED WHEN A ROADWAY IS IN A STOP OR YIELD CONDITION AND THE PROJECT SCOPE ALLOWS.

RECONSTRUCTION PROJECTS: ON FULL PAVEMENT REPLACEMENT PROJECTS "TABLING" OF ENTIRE CROSSWALK SHALL OCCUR WHEN FEASIBLE.

Rev.#

MILL & OVERLAY PROJECTS: "TABLING" OF FLOW LINES, IN FRONT OF THE PEDESTRIAN RAMP, IS REQUIRED WHEN THE EXISTING FLOW LINE IS GREATER THAN 2%.
WARPING OF THE BITUMINOUS PAVEMENT CAN NOT EXTEND INTO THE THROUGH LANE. TABLE THE FLOW LINE TO 2% OR AS MUCH AS POSSIBLE WHILE ADHERING TO
THE FOLLOWING CRITERIA:

1) 1.0% MIN. CROSS-SLOPE OF THE ROAD
2) 5.0% MAX. CROSS-SLOPE OF THE ROAD
3) "TABLE" FLOW LINE UP TO 4% CHANGE FROM EXISTING SLOPE IN FRONT OF PEDESTRIAN RAMP
4) UP TO 2% CHANGE IN FLOW LINE FROM EXISTING SLOPE BEYOND THE PEDESTRIAN CURB RAMP

STAND-ALONE ADA RETROFITS: FOLLOW MILL & OVERLAY CRITERIA ABOVE HOWEVER ALL PAVEMENT WARPING IS DONE WITH BITUMINOUS PATCHING ON BITUMINOUS ROADWAYS AND FULL-DEPTH APRON REPLACEMENT ON CONCRETE ROADWAYS.

Revision Issue Description

RAISING OF CURB LINES SHOULD OCCUR IN VERTICALLY CONSTRAINED AREAS.RAISE THE CURB LINES ENOUGH TO ALLOW COMPLIANT RAMPS OR AS MUCH AS POSSIBLE WHILE ADHERING TO THE FOLLOWING CRITERIA;

1) 1.0% MIN. AND 5.0% MAXIMUM CROSS-SLOPE OF THE ROAD
2) 1.0% MIN. FLOW LINE (ON EITHER SIDE OF PEDESTRIAN RAMP) TO MAINTAIN POSITIVE DRAINAGE
3) 5.0% RECOMMENDED MAX. FLOW LINE
4) LONGITUDINAL THROUGH LANE ROADWAY TAPERS SHOULD BE 1" VERTICAL PER 15'HORIZONTAL

Date

MINNESOTA DEPARTMENT

90% PLANS

STANDARD PLAN 5-297.250 6 OF 6 APPROVED: 11-04-2021 REVISED:

PEDESTRIAN CURB RAMP DETAILS

(TH SHEET NO. 0F SHEETS

REVISION APPROVED: 11-04-2021

/1 0M

NOTES:

THOMAS STYRBICKI STATE DESIGN ENGINEER

STATE PROJ. NO.

1 TO ENSURE RAMPS AND LANDINGS ARE PROPERLY CONSTRUCTED, ALL INITIAL LANDINGS AT A TOP OF A RAMPED SURFACE (RUNNING SLOPE GREATER THAN 2%) SHALL BE FORMED AND PLACED SEPARATELY IN AN INDEPENDENT CONCRETE POUR. FOLLOW SIDEWALK REINFORCEMENT DETAILS ON THIS SHEET FOR ALL SEPARATELY POURED INITIAL LANDINGS. ② DRILL AND GROUT NO. 4 12" LONG REINFORCEMENT BARS (EPOXY COATED) AT 36" MAXIMUM CENTER TO CENTER MINIMUM 12" SPACING FROM CONSTRUCTION JOINTS. BARS TO BE ADJUSTED TO MATCH RAMP GRADE. BARS TO BE PAID BY EACH.

4 THIS CURB LINE REINFORCEMENT DETAIL SHALL BE USED ON BITUMINOUS ROADWAYS. FOR CONCRETE ROADWAYS, SEE NOTE 6.

(5) CONSTRUCT WITH EXPANSION MATERIAL PER MNDOT SPECIFICATION 3702 TYPES A-E. EXPANSION MATERIAL SHALL MATCH FULL HEIGHT OF ADJACENT CONCRETE. (6) USE AN APPROVED TYPE F (1/4 INCH THICK) SEPARATION MATERIAL. SEPARATION MATERIAL SHALL MATCH FULL HEIGHT DIMENSION OF ADJACENT CONCRETE.

176070 Rev.# ACB ACB


TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS

of 42

15

SP 6614-33



BARE ROOT PERENNIALS MUST BE PLACED IN THE SPRING NO LATER THAN JUNE 1ST OR FOLLOW THE FALL DECIDUOUS PLANTING DATES.

PLANTING DATES.

2. ACTUAL DATES MAY CHANGE DEPENDING UPON SEASONAL CONDITIONS, AS DETERMINED BY THE ENGINEER.

3. FALL PLANTING IS NOT ALLOWED FOR BARE ROOT FORM OF THE FOLLOWING SPECIES: HAWTHORN, DOGWOOD, POPLAR, HACKBERRY, LINDEN, IRONWOOD, HONEYLOCUST, BIRCH, MOUNTAIN ASH, MAPLE, WILLOW, CRABAPPLE, PLUMCHERRY, OAKS, AND SUMAC.

4. ALL REPLACEMENT PLANTS MUST BE PLACED DURING THE MONTH OF MAY (SPRING PLANTING) AND SEPTEMBER (FALL PLANTING) DURING THE FIRST YEAR OF THE PLANT ESTABLISHMENT PERIOD.

5. MACHINE MOVED PLANTING DATES WILL

MACHINE MOVED PLANTING DATES WILL BE SPECIFIED IN THE SPECIAL PROVISIONS.

CANADA

PLANT INSTALLATION PERIOD

	PL/	٩N	TING DA	TES B	Y ZONI
				3	4
		DECIDUOUS	BARE ROOT	APRIL 21 TO JUNE 1	TO JUNE 1
	G	DECID	CONTAINER B&B	APRIL 21 TO JUNE 30	APRIL 7
)	SPRING	CC	ONIFEROUS	APRIL 21 TO JUNE 1	
	SF	PERENNIALS		MAY 1 TO JUNE 30	MAY 1
		s	EEDLINGS	APRIL 21 TO JUNE 1	
		snon	BARE ROOT	OCT. 1 TO NOV. 1	OCT. 10 TO NOV. 15
	⊣	DECIDNOUS	CONTAINER B&B	AUG. 25 TO OCT. 15	AUG. 25 TO NOV. 1
	FALL	C	NIFEROUS	AUG. 25 TO SEPT. 15	AUG. 25 TO SEPT. 15
		P	ERENNIALS	AUG. 25 TO SEPT. 15	AUG. 25 TO SEPT. 15

ACCEPTABLE ZONES

ZONES LEGEND MIN. TEMP.

UNACCEPTABLE ZONES

ZONES LEGEND

-34.4° TO -40 F

-28.9° TO -34.4 F

-26.1°TO -28.9 F

LIVE BRANCH BRANCH BARK RIDGE DEAD BRANCH RANCHES PRUNED AT TRUNK

CORRECT TOO TOO TOO

CLOSE LONG SLANTED LIVE BUD

BRANCHES PRUNED TO LIVE BUD

PRUNING

STEPS TO PRUNING WITH PRUNING SAW

- **CUT PART WAY THROUGH THE**
- BRANCH AT POINT A. CUT COMPLETELY THROUGH
- BRANCH FROM POINT B TO A. 3. AT BRANCH COLLAR CUT FROM POINT C TO D.


INCORRECT CUT FROM POINT C TO X (TOO CLOSE) WILL RESULT IN DISCONTINUOUS CALLUS FORMATION AFTER ONE SEASON OF GROWTH.

CORRECT CUT FROM POINT C TO D (LEAVING BRANCH COLLAR BUT NOT THE STUB FROM POINT B TO A) WILL RESULT IN CONTINUOUS DOUGHNUT SHAPED CALLUS FORMATION AFTER ONE SEASON OF GROWTH.

PRUNING NOTES:


- 1. PRUNE USING CLEAN AND SHARP SCISSOR-TYPE PRUNER OR PRUNING SAW.
- 2. THE BEST TIME TO PRUNE IS LATE DORMANT SEASON OR EARLY SPRING
- 3. AVOID PRUNING OAKS IN APRIL MAY, JUNE OR JULY.
- IF PRUNING IS NECESSARY OR IF WOUNDS OCCUR TO OAK TREES IN APRIL, MAY, JUNE OR JULY, IMMEDIATELY PAINT CUT SURFACE OR WOUND WITH LATEX PAINT OR SHELLAC.

(MnDOT 2571.3E.1 and 2571.3K.2.a(9))



CULTIVATED INPLACE SOIL DEPTH (MnDOT 2571.3D.2)

PRIMARY TILLAGE - PASS 1



4 INCHES OF GRADE 2 COMPOST AND OTHER SPECIFIED ADDITIVES THOROUGHLY MIXED WITH INPLACE CULTIVATED SOILS

INCORPORATION TILLAGE - PASS 2

PLANTING SOIL

(MnDOT 2571.3D)

REVISION

176070

ACB

ACB

APPROVED: DECEMBER 11, 2015 Loop. Clil

Rev.#

ACCEPTABLE PLANT STOCK GROWING RANGE LIMITS SOURCE: USDA PLANT HARDINESS ZONE MAP (MnDOT 3861.2C)

YEARS WITHIN THE ACCEPTABLE LIMITS SHOWN.

FOR ALL PLANT STOCK, DOCUMENT ACCEPTABILITY FOR HARDINESS IN THE

A. PLANT STOCK CONTINUOUSLY GROWN FOR AT LEAST THE LAST TWO

B. PLANT STOCK, GROWN OUTSIDE THE ACCEPTABLE GROWING RANGE

LIMITS, HAVING SEED SOURCE OR ROOT AND GRAFT STOCK ORIGINATING FROM THE ACCEPTABLE LIMITS SHOWN

MINNESOTA ZONE WHERE THE PROJECT SITE IS LOCATED. AS FOLLOWS:

MINNESOTA 10m DEPARTMENT

STANDARD PLAN 5-297.301

APPROVED: 12-11-2015 REVISED:

STATE PROJ. NO.

1 OF 3

STANDARD PLANTING DETAILS

(T.H. SHEET NO. OF SHEETS

Revision Issue Description

90% PLANS

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS

16

of 42 SP 6614-33


SEH Project

REQUIREMENTS.

Date Rev.#

HOLE DEPTH FOR B&B AND CONTAINER PLANTS SHALL NOT EXCEED MEASUREMENT FROM ROOT

FLARE TO BOTTOM OF SOIL BALL.			
PLANT TYPE	PLANT SIZE UP TO AND INCLUDING	(A) MINIMUM HOLE WIDTH	(B) APPROXIMATE HOLE DEPTH
	3' B.R.	46"	13"
	4' B.R	46"	14"
	5' B.R.	48"	14"
	6' B.R.	54"	15"
	7' B.R	60"	16"
l	8' B.R.	66"	19"
	0.75" B.R.	48'	12"
	1" B.R.	54"	14"
l	1.25" B.R.	60"	14"
	1.5 B.R.	66"	15"
	1.75" B.R	72"	16"
l	2" B.R.	84"	19"
DECIDUOUS &	4' B.B.	42"	11"
ORNAMENTAL	5' B.B.	48"	12"
TREES	6' B.B.	52"	14"
l	8' B.B.	66"	16"
	10' B.B.	66"	16"
	12' B.B.	48"	16"
l	1" B.B.	54"	14"
	1.25" B.B.	56"	15"
	1.5" B.B.	61"	15"
	1.75" B.B.	66"	16"
l	2" B.B.	72"	16"
	2.5" B.B.	84"	19"
	3" B.B.	96"	20"
l	3.5" B.B.	114"	23"
	4" B.B.	126"	25"
	12" B.R.	24"	7"
DECIDUOUS	15" B.R.	28"	8″
	18" B.R.	30"	8″
SHRUBS, ROSES AND PERENNIALS	2' B.R.	33"	9"
AND PEREININIALS	3' B.R.	42"	11″
	4' B.B.	48"	12"
	5′ B.R.	54"	14"
	6' B.R.	60"	14"
PERENNIAL HOLE DEPTH AND WIDTH	18" B.B.	27"	7"
SHALL BE BASED	2' B.B.	30"	8"
UPON ON-CENTER	3' B.B.	36"	9"
SPACING IN A CONTINUOUS TRENCH.	4' B.B.	42"	11″
CONTINUOUS INENCH.	5' B.B.	48"	12"
I	6' D D	EA"	14"




Revision Issue Description

INSTALLATION OF VINES


REVISION: APPROVED: DECEMBER 11, 2015

Rev.#



- 1. SCARIFY SIDES AND BOTTOM OF HOLE.
- 2. PROCEED WITH CORRECTIVE PRUNING
- 3. SET PLANT ON UNDISTURBED NATIVE SOIL OR THOROUGHLY COMPACTED PLANTING SOIL. PLACE PLANT SO THE ROOT FLARE IS AT OR UP TO 2" ABOVE THE FINISHED GRADE WITH BURLAP AND WIRE BASKET, (IF USED), INTACT.
- SLIT REMAINING TREATED BURLAP AT 6" INTERVALS.
- 5. BACKFILL TO WITHIN APPROXIMATELY 12" OF THE TOP OF THE ROOTBALL, THEN WATER PLANT.
- 6. REMOVE THE TOP 1/3 OF THE BASKET OR THE TOP TWO HORIZONTAL RINGS WHICHEVER IS GREATER. REMOVE ALL BURLAP AND NAILS FROM THE TOP 1/3 OF THE BALL. REMOVE ALL TWINE, REMOVE OR CORRECT STEM GIRDLING ROOTS.
- 7. PLUMB AND BACKFILL WITH PLANTING SOIL.
- 8. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANTS AND FILL VOIDS.
- 9. BACK FILL VOIDS AND WATER A SECOND TIME.
- 10. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.


BALLED & BURLAPPED STOCK



- 1. SOAK ROOTS IN WATER FOR AT LEAST ONE HOUR BUT NOT MORE THAN 24 HOURS PRIOR TO PLANTING.
- 2. SCARIFY SIDES AND BOTTOM OF HOLE.
- 3. PROCEED WITH CORRECTIVE PRUNING OF THE TOP AND ROOTS.
- 4. TRANSFER PLANT DIRECTLY FROM WATER TO HOLE. SET PLANT SO THE ROOT FLARE IS AT THE FINISHED SOIL ELEVATION. SPREAD ROOTS OUT EVENLY. PLUMB AND IMMEDIATELY BACKFILL WITH PLANTING SOIL.
- 5. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANTS AND FILL VOIDS
- 6. BACK FILL VOIDS AND WATER A SECOND TIME. 7. PLACE MULCH WITHIN 48 HOURS OF THE SECOND
- WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.


BARE ROOT STOCK

INSTALLATION OF PLANTS



- 1. SCARIFY SIDES AND BOTTOM OF HOLE.
- 2. PROCEED WITH CORRECTIVE PRUNING OF TOP AND ROOT.
- 3. REMOVE CONTAINER AND SCORE OUTSIDE OF SOIL MASS TO REDIRECT AND PREVENT CIRCLING FIBROUS ROOTS. REMOVE OR CORRECT STEM GIRDLING ROOTS.
- 4. SET PLANT ON UNDISTURBED NATIVE SOIL OR THOROUGHLY COMPACTED PLANTING SOIL. INSTALL PLANT SO THE TOP OF THE ROOT FLARE IS AT OR UP TO 2" ABOVE THE FINISHED GRADE.
- 5. PLUMB AND BACKFILL WITH PLANTING SOIL
- 6. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANT AND FILL VOIDS.
- 7. BACK FILL VOIDS AND WATER A SECOND TIME.
- 8. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.

CONTAINER STOCK



- 1. SCARIFY SIDES AND BOTTOM OF HOLE.
- 2. PROCEED WITH CORRECTIVE PRUNING.
- 3. SET PLANT ON NATIVE SOIL AT SAME DEPTH AS IT WAS PREVIOUSLY GROWN.
- 4. PLUMB AND BACKFILL WITH PLANTING SOIL
- 5. AFTER PLANTING, LOOSEN THE SOIL IMMEDIATELY ADJACENT TO THE ROOT BALL TO A MINIMUM DISTANCE OF 18" AND A MINIMUM DEPTH OF 12".
- 6. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANT AND FILL VOIDS.
- 7. BACK FILL VOIDS AND WATER A SECOND TIME.
- 8. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.

MINIMUM	TREE SPADE	SIZE REQU	IREMENTS
(C) SPADE DIAMETER SIZE	OAK TREE, CALIPER	DECIDUOUS / ORNAMENTAL TREE,CALIPER	CONIFEROUS TREE, HEIGHT
42"	1" to 1.5"	2" to 3"	5' to 7'
60"	1.5" to 2.5"	3" to 4"	7' to 9'
78"	2.5" to 3.5"	4" to 6"	9' to 14'
85"	3.5" to 5"	6" to 8"	14' to 18'

MACHINE MOVED STOCK

(MnDOT 2

2 OF 3

	MULCH		
2571.3F)			
	STANDARD	PLANTING	DETAILS

MINNESOTA DEPARTMENT

STANDARD PLAN 5-297.301 10m

APPROVED: 12-11-2015 REVISED: STATE PROJ. NO.

(T.H. 0F SHEETS SHEET NO.

PLANTING HOLE DIMENSIONS

HOLE DEPTH FOR B&B AND CONTAINER PLANTS SHALL NOT EXCEED MEASUREMENT FROM ROOT FLARE TO BOTTOM OF SOIL BALL.

MINIMUM HOLE

MULCH AREA CALCULATOR

SQ. FT. PER PLANT

 $\left[\frac{3 / 5 \times HEIGHT}{2}\right]^{2} \times \Upsilon$

3² x TY

SPACING x SPACING

SPACING x 2

(SPADE DIAMETER)+1 X TY

TY = 3.1416

(MnDOT 2571.3H)

(B) APPROXIMATE

PLANT SIZE UP TO (A)

8' B.B 9' B.B

CELLPACKS / PLUGS

2.25" CONT 3.5" CONT

6"/1 QT CON

2# CONT

20# CONT 25# CONT

6" SEEDLING

9" SEEDLING

12" SEEDLING 18" SEEDLING

1 YR. NO. 1 B.R.

TYPE OF PLANT

CONIFEROUS TREES

ORNAMENTAL TREES

DECIDUOUS SHRUBS,

ORNAMENTAL GRASS

DECIDUOUS AND

CONIFEROUS AND

MACHINE-MOVED

TREES OR SHRUBS

ROSE BUSHS.

PERENNIAI S

VINES

SPÄCING FROM TRUNK

CONIFEROUS, TREE (RADIUS + 3' mjp.)

DECIDUOUS TREE (3' min.)

DECIDUOUS SHRUB (3'min.)

TRANSPLANT (RADIUS + 2' min.)

CONIFEROUS AND

PLANT TYPE

LEAST 2/3 OF A CONIFER BRANCHE WILL CONTAIN

CONIFEROUS

SHRUBS

(UPRIGHT)
CONIFEROUS

SHRUBS

(SPREADING)

CONTAINER GROWN PLANTS

SEEDLINGS

VINES

SEH Project 176070 ACB ACB

Revision Issue Description

Date

Rev.#

90% PLANS


TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

MNDOT STANDARD PLANS

17

- 1. EXCAVATE HOLE OR BED TO ALLOW PLACING THE TOP OF ROOT MASS 1"-3" HIGHER THAN FINISHED GRADE
- 2. AUGER 8" DIAMETER HOLES ENTIRELY THROUGH IMPERVIOUS OR POORLY DRAINED HARD PAN SOIL LAYER TO ADEQUATELY DRAIN SUBSOIL
- 3. TEST FOR POSITIVE DRAINAGE. RE-AUGER AN ADDITIONAL 8" IF NECESSARY FOR POSITIVE
- 4. THOROUGHLY BACKFILL AUGER HOLES WITH A UNIFORM INCORPORATED MIXTURE OF 50% SAND AND 50% INPLACE SOIL. 5. COMPLETE PLANTING ACCORDING TO ROOT TYPE. SEE STANDARD PLANTING DETAILS (2 OF 3).


GRANULAR FILTER



- 1. EXCAVATE HOLE OR BED TO ALLOW PLACING THE TOP OF THE ROOT MASS 1"-3" HIGHER THAN FINISHED GRADE.
- 2. INSTALL 4" MINIMUM DIAMETER DRAIN TILE DAYLIGHTING AT A LOWER GRADE.

 3. COMPLETE PLANTING ACCORDING TO ROOT TYPE. SEE STANDARD PLANTING DETAILS (2 OF 3).

TILE DRAINAGE



- 1. EXCAVATE HOLE OR BED 1/4 THE DEPTH OF THE ROOT MASS.
- 2. SET ROOT MASS IN HOLE.
- 3. CONSTRUCT BERM WITH PLANTING SOIL. EXTEND THE BERM BASE TO A WIDTH OF 3 TIMES THE BERM HEIGHT.
- 4. COMPLETE PLANTING ACCORDING ROOT TYPE. SEE STANDARD PLANTING DETAILS (2 OF 3).

MINI-BERM

1. THE NEED FOR USING PLANTING DETAILS FOR POORLY DRAINED SOILS AND WHICH TYPE TO USE ARE DETERMINED BY THE CONTRACTOR, SUBJECT TO ENGINEER APPROVAL


Date

Rev.#


PLANTING DETAIL FOR POORLY DRAINED SOILS

(MnDOT 2571.3D.2(8))

Revision Issue Description



FOR MULCH DETAIL SEE STANDARD PLANTING DETAIL (2 OF 3) SOIL RIDGE TO HOLD WATER IN BASIN. DOWN HILL HALF PLANT ACCORDING TO ROOT TYPE. SEE STANDARD PLANTING DETAILS (2 OF 3) FOR PLANTING SOIL DETAIL SEE STANDARD PLANTING DETAILS (1 OF 3) **PLANTING ON SLOPES**



- 1. FORM A DOUBLE-LAYERED CYLINDER USING 0.25" GRID GALVANIZED WELDED WIRE MESH (HARDWARE
- 2. DRIVE TWO 1" x 1" OPPOSING HEARTWOOD WHITE OAK STAKES INTO THE GROUND. 7" FROM THE
- A SECURE THE MESH CYLINDER TO THE OUTSIDE OF THE STAKES USING EITHER, SCREWS AND WASHERS OR CABLE-TIES ALONG THE OVERLAP.

 BYPACE APPROXIMATELY 4" ON CENTER ALONG THE OVERLAP.

 CABLE-TIES ALONG THE OVERLAP.

 BYPACE APPROXIMATELY 4" ON CENTER ALONG THE OVERLAP.

 CABLE-TIES ALONG THE OVERLAP.

 BYPACE APPROXIMATELY 4" ON CENTER ALONG THE OVERLAP.

 CABLE-TIES ALONG THE THE OUTSIDE OF THE STAKES USING EITHER, SCREWS AND WASHERS.


b. CABLE-TIES SHALL BE NYLON, AT LEAST 8" LONG AND BETWEEN 75LB TO 120LB TENSILE STRENGTH

- 4. EMBED THE LOWER EDGE OF THE MESH CYLINDER 1" BELOW THE SOIL SURFACE WITHOUT DISTURBING THE TREE ROOTS
- 5. CUT EDGES WILL NOT BE PERMITTED AT THE TOP OF THE CYLINDER. STAKE WILL BE FLUSH WITH THE TOP OF THE CYLINDER.
- 6. MULCH WITHIN THE CYLINDER SHALL NOT EXCEED 3" DEPTH AND SHALL BE PULLED BACK FROM THE
- TRUNK AS SPECIFIED IN MULCH PLACEMENT DETAIL.

 7. THE BOTTOM WHORL OF PINE AND LARCH BRANCHES MAY HAVE TO BE REMOVED TO PERMIT INSTALLATION OF 12" MIN. HEIGHT RODENT GUARDS.
- 8. INSTALL ON ALL DECIDUOUS, PINE AND LARCH TREES, DO NOT PLACE ON SPRUCE TREES.

RODENT PROTECTION

- USE SEAMLESS, EXTRUDED, TWIN-WALL, RIGID AND SEMI TRANSLUCENT POLYPROPYLENE TUBES WITH A LASER LINE PERFORATION AND AN OUTWARD-FLARED TOP RIM
- SECURE SHELTER WITH NYLON CABLE-TIES ATTACHED TO A 1" x 1" WHITE OAK STAKE TO PREVENT DISLODGING OR TWISTING
- EMBED THE BOTTOM OF THE TUBE A MINIMUM OF 1" BELOW THE SOIL SURFACE WITHOUT DISTURBING THE TREE ROOTS.
- PLACE A PLASTIC
 PHOTODEGRADABLE NETTING COVER AND SLEEVE OVER THE TOP OF THE TUBE. PULL NETTING DOWN AS SHOWN



SEEDLING TREE SHELTER

(MnDOT 2571.3I.2)


PLANT SPACING IN MASS BEDS

FOR MULCH DETAIL

SEE STANDARD

(2 OF 3)

PLANTING DETAIL



16" LONG POLYROPYLENE OR POLYETHYLENE, 40 MIL THICK AND 1.5" WIDE STRAPS, ATTACH WITH 10 ga WIRE.

HOLE EXCAVATION WIDTH IN ACCORDANCE WITH

MINIMUMS FROM THE PLANTING HOLE DIMENSIONS

FOR PLANTING SOIL

- DETAIL SEE STANDARD

PLANTING DETAILS (1 OF 3)

5' FOR DECIDUOUS TREES

8' FOR CONIFEROUS TREES

CHART ON STANDARD PLANTING DETAILS (2 OF 3)

- 1. STEEL POSTS TO BE NOTCHED OR DRILLED TO RETAIN GUY WIRES. PLACE OUTSIDE OF ROOT BALL. DRIVE PLUMB REGARDLESS OF GROUND
- 2. REQUESTS TO SUBSTITUTE RUBBER HOSE AND WIRE **GUYING SYSTEMS WILL NOT** BE APPROVED
- 3. TREE STAKING IS NOT REQUIRED UNLESS SPECIFIED OR NECESSARY TO MAINTAIN TREES IN A PLUMB CONDITION WHERE VANDALISM, SOIL, OR WIND CONDITIONS ARE A PROBLEM, OR AS DIRECTED BY THE ENGINEER.
- 4. REMOVE WITHIN ONE YEAR.

STEEL POST SIZING					
CALIPER	STEEL POST TYPE	Α	В	С	D
LESS THAN 4 INCHES	HOT-ROLLED STEEL FENCE POST (Mn/DOT 3403) OR APPROVED EQUAL.	7′–0″	3'-0" MIN.	4'-0"	3′–0″
GREATER THAN 4 INCHES	10', 2.2 LB. FLANGED CHANNEL SIGN POST (Mn/DOT 3401) OR APPROVED EQUAL.	10'–0"	4'-0" MIN.	6′–0″	5′–0″

STAKING AND GUYING

(MnDOT 2571.3I.1)

REVISION: APPROVED: DECEMBER 11, 2015 MINNESOTA DEPARTMENT

10m

STANDARD PLAN 5-297.301 3 OF 3 APPROVED: 12-11-2015 REVISED:

STATE PROJ. NO.

STANDARD PLANTING DETAILS

(T.H. SHEETS SHEET NO. 0F

Revision Issue Description SEH Project 176070 Rev.# ACB

ACB


90% PLANS


TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA


MNDOT STANDARD PLANS

18 of 42

SP 6614-33







WILLIAM BAUER, PE

NORTHFIELD, MINNESOTA

ACB


ACB

20

SP 6614-33 of 42

TRAIL AND STORM SEWER PLAN AND PROFILE





HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION OF THAT ANY AM A DULY LICENSED PROFFESIONAL ENGINEER UNDER THE LAWSO THE STATE OF MINNESOTA.

WILLIAM BAUER, PE

ACB

ACB

Checked By


TRUNK HIGHWAY 246 TRAIL


NORTHFIELD, MINNESOTA


21

SP 6614-33 of 42

TRAIL AND STORM SEWER PLAN AND PROFILE








PREFABRICATED MODULAR BLOCK WALL

WALL C - STA. 8+90 TO STA. 12+19



COPING AND FENCING CONNECTION DETAIL


NOT TO SCALE

KEYNOTES:


- 1. VERIFY WITH BLOCK MANUFACTURER FOR RETAINING WALL UNIT
- 2. WIRE FENCE DESIGN 48V-9322.
- 3. CONCRETE SHALL BE MIX 3B52 (MNDOT 2461). REINFORCEMENT SHALL BE EPOXY COATED.
- 4. PMBW DESIGN ENGINEER TO PROVIDE REQUIREMENTS FOR RAILING AND BLOCK ANCHORAGES AND ENSURE COPING AND BLOCK SYSTEM PROVIDE REQUIRED RESISTANCE FOR PEDESTRIAN AND BICYCLIST RAILING.

PREFABRICATED MODULAR BLOCK WALL NOTES:

- 1. MINIMUM REINFORCEMENT LENGTH MEASURED FROM THE BACK FACE OF THE BLOCK.
- 2. 4" NOMINAL DIAMETER PERFORATED PIPE IN ACCORDANCE WITH SPEC. 3245.2 MEETING ASTM D1785. WRAP WITH TYPE 1 GEOTEXTILE IN ACCORDANCE WITH SPEC. 3733. INSTALLATION IN ACCORDANCE WITH SPEC, 2502.
- 3. PAY LIMITS. ACTUAL EXCAVATION SLOPE IS DETERMINED BY OSHA REGULATIONS AND IN-SITU SOILS: EXCAVATION BEYOND THESE LIMITS AT CONTRACTORS EXPENSE.
- SCARIFY SOILS BELOW CONCRETE LEVELING PAD TO A DEPTH OF 6" AND RECOMPACT TO 100% OF STANDARD PROCTOR MAXIMUM DENSITY.
- 5. PREFABRICATED MODULAR BLOCKS UNITS SHALL CONSIST OF WET CAST CONCRETE UNITS AS REQUIRED IN ACCORDANCE WITH THE SPECIAL PROVISIONS.
- 6. PLACE 6" TOPSOIL AND PROVIDE TURF ESTABLISHMENT ACCORDING TO THE EROSION CONTROL AND TURF ESTABLISHMENT SHEETS.
- 7. DUE TO WALL BATTER AND VERTICAL GRADE CHANGE ALONG THE LENGTH OF THE WALL, ADJUST BASE BLOCK ALIGNMENT AS NEEDED TO MAINTAIN THE TRAIL
- 8. DRAIN TILE TO BE DAYLIGHTED AT ELEVATION 963 FEET AT TOE OF EMBANKMENT NEAR TRAIL STA 7+00. DRAIN TILE FROM END OF WALL TO DAYLIGHT TO BE 6IN NON-PERFORATED T.P.IN ACCORDANCE WITH THE SPECIAL PROVISIONS.



LEVELING PAD DETAIL



Revision Issue Description SEH Project 176070 Rev.# Date Rev.# ACB Drawn By ACB

Checked By

WB




I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION OF THAT I AM A DULY LICENSED PROFFESIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA. WILLIAM BAUER PE LICENSE NO

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

RETAINING WALL DETAILS

24



COMBINATION OF NARRATIVE AND PLAN SHEETS THAT DESCRIBE THE TEMPORARY AND PERMANENT STORM WATER MANAGEMENT PLAN FOR THE PROJECT.

PROJECT INFORMATION:

LOCATION:	NORTHFIELD, MINNESOTA
LATITUDE/LONGITUDE:	44.4431, -93.1605
PROJECT DESCRIPTION:	TRAIL EXPANSION
SOIL DISTURBING ACTIVITIES:	GRADING, STORM SEWER AND RETAINING WALL INSTALLATION

CONTACTS

CONTACTO.	
OWNER:	CITY OF NORTHFIELD
CONTACT:	SEAN SIMONSON
ADDRESS:	801 WASHINGTON ST, NORTHFIELD, MN 55057
PHONE:	507.645.3049
EMAIL:	SEAN.SIMONSON@NORTHFIELDMN.GOV
ENGINEER:	SHORT ELLIOTT HENDRICKSON INC. (SEH)
CONTACT:	WILLIAM BAUER, PE
PHONE:	952.912.2629
EMAIL:	wbauer@sehinc.com
PROJECT NO.:	NF176070
ALOUAU EDOEADI	PERSONAL VALUE PERSONAL PROPERTY

KNOWLEDGEABLE PERSON/CHAIN OF RESPONSIBILITY
THE CONTRACTOR SHALL IDENTIFY A PERSON KNOWLEDGEABLE AND EXPERIENCED IN THE APPLICATION OF EROSION PREVENTION AND SEDIMENT CONTROL BMPS WHO WILL COORDINATE WITH ALL CONTRACTORS, SUBCONTRACTORS, AND OPERATORS ON-SITE TO OVERSEE THE IMPLEMENTATION OF THE SWPPP.

CONTRACTOR	X
CONTACT	X
PHONE	X
EMAIL	X


THE CONTRACTOR SHALL ESTABLISH A CHAIN OF RESPONSIBILITY FOR ALL CONTRACTORS AND SUB-CONTRACTORS ON SITE TO ENSURE THE SWPPP IS BEING PROPERLY IMPLEMENTED AND MAINTAINED. THE CONTRACTOR SHALL PROVIDE THE CHAIN OF RESPONSIBILITY TO THE OWNER AND ATTACH TO THE SWPPP PRIOR TO ANY CONSTRUCTION ACTIVITY.

GENERAL SWPPP RESPONSIBILITIES:
THE CONTRACTOR SHALL KEEP THE SWPPP, INCLUDING ALL AMENDMENTS AND INSPECTION AND MAINTENANCE RECORDS ON SITE DURING CONSTRUCTION.

THE SWPPP WILL BE AMENDED AS NEEDED AND/OR AS REQUIRED BY PROVISIONS OF THE PERMIT. PERMITTEES MUST AMEND THE SWPPP TO INCLUDE ADDITIONAL OR MODIFIED BMPS AS NECESSARY TO CORRECT PROBLEMS IDENTIFIED OR ADDRESS SITUATIONS WHENEVER THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, MAINTENANCE, WEATHER OR SEASONAL CONDITIONS HAVING A SIGNIFICANT EFFECT ON THE DISCHARGE OF POLLUTANTS TO SURFACE WATERS OR GROUNDWATER. AMENDMENTS WILL BE APPROVED BY BOTH THE OWNER AND CONTRACTOR AND WILL BE ATTACHED OR OTHERWISE INCLUDED WITH THE SWPPP DOCUMENTS. THE SWPPP AMENDMENTS SHALL BE

ALL SWPPP CHANGES MUST BE DONE BY AN INDIVIDUAL TRAINED IN ACCORDANCE WITH SECTION 21.2. CHANGES INVOLVING THE USE OF A LESS STRINGENT BMP MUST INCLUDE A JUSTIFICATION DESCRIBING HOW THE REPLACEMENT BMP IS EFFECTIVE FOR THE SITE CHARACTERISTICS.

BOTH THE OWNER AND CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER TERMINATION AND/OR TRANSFER OF THE PERMIT.



TRAINING DOCUMENTATION:

PREPARER/DESIGNER OF SWPPP:	MATHEW STEELY
EMPLOYER:	SHORT ELLIOTT HENDERICKSON INC. (SEH®)
DATE OBTAINED / REFRESHED	REFRESHED JANUARY 2024
INSTRUCTOR(S)/ENTITY PROVIDING TRAINING:	UNIVERSITY OF MINNESOTA

CONTENT OF TRAINING AVAILABLE UPON REQUEST.

THE CONTRACTOR (OPERATOR) SHALL ADD TO THE SWPPP TRAINING RECORDS FOR THE

-INDIVIDUALS OVERSEEING THE IMPLEMENTATION OF, REVISING, AND AMENDING THE SWPPP -INDIVIDUALS PERFORMING INSPECTIONS -INDIVIDUALS PERFORMING OR SUPERVISING THE INSTALLATION, MAINTENANCE AND REPAIR

TRAINING MUST RELATE TO THE INDIVIDUAL'S JOB DUTIES AND RESPONSIBILITIES AND SHALL

1) DATES OF TRAINING

2) NAME OF INSTRUCTORS

3) CONTENT AND ENTITY PROVIDING TRAINING

THE CONTRACTOR SHALL ENSURE THAT THE INDIVIDUALS ARE TRAINED BY LOCAL. STATE. FEDERAL AGENCIES, PROFESSIONAL ORGANIZATIONS, OR OTHER ENTITIES WITH EXPERTISE IN EROSION PREVENTION, SEDIMENT CONTROL, PERMANENT STORMWATER MANAGEMENT AND THE MINNESOTA NPDES/SDS CONSTRUCTION STORMWATER PERMIT.

PROJECT SUMMARY:

TOTAL DISTURBED AREA:	0.86 AC
PRE-CONSTRUCTION IMPERVIOUS AREA:	0.15 AC
POST-CONSTRUCTION IMPERVIOUS AREA:	0.29 AC
IMPERVIOUS AREA ADDED:	0.14 AC

ID	NAME	TYPE	SPECIAL WATER?	IMPAIRED WATER?	CONSTRUCTION RELATED IMPAIRMENT OR SPECIAL WATER CLASSIFICATION	TMDL		
	CANNON RIVER	RIVER	N	Y	Impairment(s) are considered to be construction related parameters and require the additional best management practices (BMPs) found in items 23.9 and 23.10 o			
	NO NAME	CREEK	N	N				
ADDITIONA	ADDITIONAL BMPS AND/OR ACTIONS REQUIRED:							

, is sintered as a subject, the next of the quite sintered as a subject of the property of the
SEE SECTION 23 OF THE PERMIT AND APPLICABLE TMDL WLA'S

WATERBODY	NO WORK DURING
LAKES	APRIL 1 - JUNE 30
NON-TROUT STREAMS	MARCH 15 - JUNE 15
TROUT STREAMS	SEPTEMBER 1 - APRIL 1

SEE DNR PERMIT FOR MORE

SITE SOIL INFORMATION: (http://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx)
(SOIL INFORMATION PROVIDED IS FOR NPDES PERMIT INFORMATION ONLY. SOIL INFORMATION WAS OBTAINED FROM THE USGS WEBSITE. THE CONTRACTOR SHALL NOT RELY ON THIS SOIL INFORMATION FOR CONSTRUCTION PURPOSES.)

SOIL NAME:	HYDROLOGIC CLASSIFICATION:
ESTHERVILLE SANDY LOAM, 41A	A
URBAN LAND ESTHERVILLECOMPLEX, 849B	A
ANTICIPATED RANGE OF PARTICLE SIZES	

RELATED REVIEWS & PERMITS: ENVIRONMENTAL, WETLAND, ENDANGERED OR THREATENED SPECIES, ARCHEOLOGICAL LOCAL, STATE, AND/OF FEDERAL REVIEWS/PERMITS:

AGENCY:	TYPE OF PERMIT:
EPA	NPDES PERMIT
MnDOT	LIMITED USE PERMIT
MnDOT	MISCELLANEOUS WORK PERMIT

LONG TERM OPERATION AND MAINTENANCE

THE OWNER WILL BE RESPONSIBLE OR WILL OTHERWISE IDENTIFY WHO WILL BE RESPONSIBLE FOR THE LONG TERM OPERATION AND MAINTENANCE OF THE PERMANENT STORMWATER

THE OWNER WILL PREPARE AND IMPLEMENT A PERMANENT STORMWATER TREATMENT SYSTEM(S) MAINTENANCE PLAN.

IMPLEMENTATION SEQUENCE:
THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING SEQUENCE THE ENGINEER MAY APPROVE ADJUSTMENTS TO THE SEQUENCE AS NEEDED.

1.	INSTALL ROCK CONSTRUCTION ENTRANCE(S)
2.	INSTALL PERIMETER CONTROL AND STABILIZE DOWN GRADIENT BOUNDARIES
3.	INSTALL INLET PROTECTION ON EXISTING CATCH BASINS
4.	COMPLETE SITE GRADING
5.	INSTALL UTILITIES, STORM SEWER, INLET PROTECTION, CURB & GUTTER, PAVING
6.	COMPLETE FINAL GRADING AND STABILIZE DISTURBED AREAS
7.	AFTER CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED, REMOVE ACCUMULATED SEDIMENT, REMOVE BMPS, AND RE-STABILIZE ANY AREAS DISTURBED BY THEIR REMOVAL.
8.	INSTALL FILTRATION MEDIA

PROJECT SPECIFIC NOTES:

THE FOLLOWING DOCUMENTS ARE CONSIDERED PART OF THE SWPPP: PLAN AND PROFILE PLAN SHEETS: EROSION AND SEDIMENT CONTROL PLAN SHEETS: TURF ESTABLISHMENT PLAN SHEETS: STORM SEWER PLAN & PROFILE PLAN SHEETS: GRADING PLAN SHEETS: DETAIL PLAN SHEETS: SWPPP NOTE AND DETAIL SHEETS PROJECT SPECIFICATIONS: PROJECT BID FORM:

TEMPORARY BMP DESIGN FACTORS: EROSION PREVENTION AND SEDIMENT CONTROL BMP'S MUST BE DESIGNED TO ACCOUNT FOR:

THE EXPECTED AMOUNT, FREQUENCY, INTENSITY, AND DURATION OF PRECIPITATION

THE NATURE OF STORMWATER RUNOFF AND RON-ON AT THE SITE, INCLUDING FACTORS SUCH AS EXPECTED FLOW FROM IMPERVIOUS SURFACES, SLOPES, AND SITE DRAINAGE FEATURES

THE STORMWATER VOLUME, VELOCITY, AND PEAK FLOW RATES TO MINIMIZE DISCHARGE OF POLLUTANTS IN STORMWATER AND TO MINIMIZE CHANNEL AND STREAMBANK EROSION AND SCOUR IN THE IMMEDIATE VICINITY OF DISCHARGE POINTS

THE RANGE OF SOIL PARTICLE SIZES EXPECTED TO BE PRESENT.

TEMPORARY SEDIMENT BASINS:
THE CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT BASIN(S) INDICATED ON PLANS AND REQUIRED BY THE NPDES CONSTRUCTION PERMIT.

THE TEMPORARY BASIN MUST PROVIDE LIVE STORAGE FOR A CALCULATED VOLUME OF RUNOFF FROM A TWO (2)-YEAR, 24-HOUR STORM FROM EACH ACRE DRAINED TO THE BASIN OR 1,800 CUBIC FEET OF LIVE STORAGE PER ACRE DRAINED, WHICHEVER IS GREATER.

TEMPORARY SEDIMENT BASIN OUTLETS SHALL BE CONSTRUCTED TO PREVENT SHORT-CIRCUITING AND PREVENT THE DISCHARGE OF FLOATING DEBRIS

OUTLET STRUCTURES MUST BE DESIGNED TO WITHDRAW WATER FROM THE SURFACE TO MINIMIZE

BASINS MUST INCLUDE A STABILIZED EMERGENCY OVERFLOW, WITHDRAW WATER FROM THE SURFACE, AND PROVIDE ENERGY DISSIPATION AT THE OUTLET.

TEMPORARY SEDIMENT BASINS SHALL BE PROVIDED WITH ENERGY DISSIPATION AT ANY BASIN OUTLIFT TO PREVENT SOIL FROSION

SEDIMENT BASINS MUST BE SITUATED OUTSIDE OF SURFACE WATERS AND ANY BUFFER ZONES, AND MUST BE DESIGNED TO AVOID THE DRAINING WATER FROM WETLANDS.

PERMANENT STORMWATER MANAGEMENT SYSTEM

PERMANENT STORMWATER MANAGEMENT SYSTEM IS DESIGNED TO MEET THE REQUIREMENTS OF NPDES GENERAL STORMWATER PERMIT FOR CONSTRUCTION ACTIVITY





EROSION PREVENTION MEASURES SHOWN ON PLANS ARE THE ABSOLUTE MINIMUM REQUIREMENTS THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL EROSION PREVENTION MEASURES AS NECESSARY TO PROPERLY MANAGE THE PROJECT AREA.

THE CONTRACTOR SHALL PLAN AND IMPLEMENT APPROPRIATE CONSTRUCTION PRACTICES AND CONSTRUCTION PHASING TO MINIMIZE EROSION AND RETAIN VEGETATION WHENEVER

THE PERMITTEE SHALL DELINEATE AREAS NOT TO BE DISTURBED. PERMITTEE(S) MUST MINIMIZE THE NEED FOR DISTURBANCE OF PORTIONS OF THE PROJECT WITH STEEP SLOPES. WHEN STEEP SLOPES MUST BE DISTURBED, PERMITTEES MUST USE TECHNIQUES SUCH AS PHASING AND STABILIZATION PRACTICES DESIGNED

THE CONTRACTOR SHALL STABILIZE OF ALL EXPOSED SOILS IMMEDIATELY TO LIMIT SOIL EROSION. IN NO CASE SHALL ANY EXPOSED AREAS, INCLUDING STOCK PILES, HAVE EXPOSED SOILS FOR MORE THAN 7 DAYS WITHOUT PROVIDING TEMPORARY OR PERMANENT STABILIZATION. STABILIZATION MUST BE COMPLETED WITHIN 7 DAYS AFTER CONSTRUCTION ACTIVITY HAS CEASED. TEMPORARY STOCKPILES WITHOUT SIGNIFICANT CLAY, SILT, OR ORGANIC COMPONENTS DO NOT REQUIRE STABILIZATION.

DRAINAGE PATHS, DITCHES, AND/OR SWALES SHALL HAVE TEMPORARY OR PERMANENT STABILIZATION WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER OR 24 HOURS AFTER CONSTRUCTION ACTIVITY IN THE DITCH/SWALE HAS TEMPORARILY OR PERMANENTLY

THE CONTRACTOR SHALL COMPLETE THE STABILIZATION OF ALL EXPOSED SOILS WITHIN 24 HOURS THAT LIE WITHIN 200 FEET OF PUBLIC WATERS PROMULGATED "WORK IN WATER RESTRICTIONS" BY THE MN DNR DURING SPECIFIED FISH SPAWNING TIMES.

THE CONTRACTOR SHALL IMPLEMENT EROSION CONTROL BMPS AND VELOCITY DISSIPATION DEVICES ALONG CONSTRUCTED STORMWATER CONVEYANCE CHANNELS AND OUTLETS.

THE CONTRACTOR SHALL STABILIZE TEMPORARY AND/OR PERMANENT DRAINAGE DITCHES OR SWALES WITHIN 200 LINEAL FEET FROM PROPERTY EDGE, OR DISCHARGE POINT(S) WITHIN 24 HOURS AFTER CONNECTING TO A SURFACE WATER OR PROPERTY EDGE.

TEMPORARY OR PERMANENT DITCHES OR SWALES USED AS A SEDIMENT CONTAINMENT SYSTEM DURING CONSTRUCTION MUST BE STABILIZED WITHIN 24 HOURS AFTER NO LONGER BEING USED AS A SEDIMENT

THE CONTRACTOR SHALL NOT UTILIZE HYDROMULCH, TACKIFIER, POLYACRYLAMIDE OR SIMILAR EROSION PREVENTION PRACTICES AS A FORM OF STABILIZATION FOR TEMPORARY OR PERMANENT DRAINAGE DITCHES OR SWALE SECTION WITH A CONTINUOUS SLOPE OF GREATER THAN 2 PERCENT.

THE CONTRACTOR SHALL ENSURE PIPE OUTLETS HAVE TEMPORARY OR PERMANENT ENERGY DISSIPATION WITH IN 24 HOURS OF CONNECTION TO A SURFACE WATER.

THE CONTRACTOR SHALL DIRECT DISCHARGES FROM BMPS TO VEGETATED AREAS TO INCREASE SEDIMENT REMOVAL AND MAXIMIZE STORMWATER INFILTRATION. VELOCITY DISSIPATION DEVICES MUST BE USED TO PREVENT EROSION WHEN DIRECTING STORMWATER TO VEGETATED AREAS.

SEDIMENT CONTROL MEASURES AND TIMING: THE CONTRACTOR IS RESPONSIBLE FOR ALL SEDIMENT CONTROL MEASURES FOR THE PROJECT.

SEDIMENT CONTROL MEASURES SHOWN ON PLANS ARE THE ABSOLUTE MINIMUM REQUIREMENTS. THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL SEDIMENT CONTROL MEASURES AS NECESSARY TO PROPERLY MANAGE THE PROJECT AREA.

THE CONTRACTOR SHALL ENSURE SEDIMENT CONTROL MEASURES ARE ESTABLISHED ON ALL DOWN GRADIENT PERIMETERS BEFORE ANY UPGRADIENT LAND DISTURBING ACTIVITIES BEGIN. THESE MEASURES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED

A FLOATING SILT CURTAIN PLACED IN THE WATER IS NOT A SEDIMENT CONTROL BMP EXCEPT WHEN WORKING ON A SHORELINE OR BELOW THE WATERLINE. IMMEDIATELY AFTER THE SHORT TERM CONSTRUCTION ACTIVITY IS COMPLETE, PERMITTEE(S) MUST INSTALL AN UPLAND PERIMETER CONTROL PRACTICE IF EXPOSED SOILS STILL DRAIN TO A SURFACE WATER.

THE CONTRACTOR SHALL ENSURE SEDIMENT CONTROL PRACTICES REMOVED OR ADJUSTED FOR SHORT-TERM ACTIVITIES BE RE-INSTALLED IMMEDIATELY AFTER THE SHORT-TERM ACTIVITY HAS BEEN COMPLETED. SEDIMENT CONTROL PRACTICES MUST BE REINSTALLED BEFORE THE NEXT PRECIPITATION EVENT EVEN IF THE SHORT-TERM ACTIVITY IS NOT COMPLETE.

THE CONTRACTOR SHALL ENSURE STORM DRAIN INLETS ARE PROTECTED BY APPROPRIATE BMPS DURING CONSTRUCTION UNTIL ALL SOURCES WITH POTENTIAL FOR DISCHARGING TO THE INLET HAVE BEEN STABILIZED.

THE CONTRACTOR SHALL PROVIDE SILT FENCE OR OTHER EFFECTIVE SEDIMENT CONTROL AT THE BASE OF THE STOCKPILES

THE CONTRACTOR SHALL INSTALL PERIMETER CONTROL AROUND ALL STAGING AREAS, BORROW PITS, AND AREAS CONSIDERED ENVIRONMENTALLY SENSITIVE.

THE CONTRACTOR SHALL ENSURE VEHICLE TRACKING BE MINIMIZED WITH EFFECTIVE BMPS. WHERE THE BMPS FAIL TO PREVENT SEDIMENT FROM TRACKING ONTO STREETS THE CONTRACTOR SHALL CONDUCT STREET SWEEPING TO REMOVE ALL TRACKED SEDIMENT.

THE CONTRACTOR SHALL IMPLEMENT CONSTRUCTION PRACTICES TO MINIMIZE SOIL COMPACTION.

THE CONTRACTOR SHALL ENSURE ALL CONSTRUCTION ACTIVITY REMAIN WITHIN PROJECT LIMITS AND THAT ALL IDENTIFIED RECEIVING WATER BUFFERS ARE MAINTAINED.

RECEIVING WATER	NATURAL BUFFER	IS THE BUFFER BEING ENCROACHED ON?	REASON FOR BUFFER ENCROACHMENT
CANNON RIVER	3900 FT	NO	
UNNAMED CREEK	3000 FT	NO	

A 50 FOOT NATURAL BUFFER MUST BE PRESERVED OR PROVIDE REDUNDANT (DOUBLE) PERIMETER SEDIMENT CONTROLS IF NATURAL BUFFER IS INFEASIBLE.

THE CONTRACTOR SHALL NOT UTILIZE SEDIMENT CONTROL CHEMICALS ON SITE.

INSPECTION AND MAINTENANCE

ALL INSPECTIONS, MAINTENANCE, REPAIRS, REPLACEMENTS, AND REMOVAL OF BMPS IS TO BE CONSIDERED INCIDENTAL TO THE BMP BID ITEMS.

THE PERMITTEE(S) IS RESPONSIBLE FOR COMPLETING SITE INSPECTIONS, AND BMP MAINTENANCE TO ENSURE COMPLIANCE WITH THE PERMIT REQUIREMENTS.

THE PERMITTEE(S) SHALL INSPECT THE CONSTRUCTION SITE ONCE EVERY 7 DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN

THE PERMITTEE(S) SHALL DOCUMENT A WRITTEN SUMMARY OF ALL INSPECTIONS AND MAINTENANCE ACTIVITIES CONDUCTED WITHIN 24 HOURS OF OCCURRENCE. RECORDS OF EACH ACTIVITY SHALL INCLUDE THE FOLLOWING:

-DATE AND TIME OF INSPECTIONS;

-NAME OF PERSON(S) CONDUCTING INSPECTION:

-FINDINGS AND RECOMMENDATIONS FOR CORRECTIVE ACTIONS IF NECESSARY;

-DATE AND AMOUNT OF RAINFALL EVENTS:

-POINTS OF DISCHARGE OBSERVED DURING INSPECTION AND DESCRIPTION OF THE DISCHARGE -AMENDMENTS MADE TO THE SWPPP

THE PERMITTEE(S) SHALL SUBMIT A COPY OF THE WRITTEN INSPECTIONS TO THE ENGINEER AND OWNER ON A MONTHLY BASIS. IF MONTHLY INSPECTION REPORTS ARE NOT SUBMITTED, MONTHLY

THE CONTRACTOR SHALL DOCUMENT AMENDMENTS TO THE SWPPP AS A RESULT OF INSPECTION(S)

THE CONTRACTOR SHALL KEEP THE SWPPP, ALL INSPECTION REPORTS, AND AMENDMENTS ONSITE. THE CONTRACTOR SHALL DESIGNATE A SPECIFIC ONSITE LOCATION TO KEEP THE RECORDS

THE CONTRACTOR IS RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF TEMPORARY AND PERMANENT WATER QUALITY BMP'S, AS WELL AS EROSION AND SEDIMENT CONTROL BMP'S.

THE CONTRACTOR SHALL INSPECT EROSION PREVENTION AND SEDIMENTATION CONTROL BMPS TO ENSURE INTEGRITY AND EFFECTIVENESS. ALL NONFUNCTIONAL BMPS SHALL BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMPS WITHIN 24 HOURS OF FINDING. THE CONTRACTOR SHALL INVESTIGATE AND COMPLY WITH THE FOLLOWING INSPECTION AND MAINTENANCE REQUIREMENTS:

PERIMETER CONTROL DEVICES, INCLUDING SILT FENCE SHALL BE REPAIRED, OR REPLACED, WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/2 OF THE DEVICE HEIGHT. THESE REPAIRS SHALL BE MADE WITHIN 24 HOURS OF DISCOVERY.

TEMPORARY AND PERMANENT SEDIMENT BASINS SHALL BE DRAINED AND THE SEDIMENT REMOVED WHEN THE DEPTH OF SEDIMENT COLLECTED IN THE BASIN REACHES 1/2 THE STORAGE VOLUME. DRAINAGE AND REMOVAL MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY.

SURFACE WATERS, INCLUDING DRAINAGE DITCHES AND CONVEYANCE SYSTEMS, MUST BE INSPECTED FOR EVIDENCE OF EROSION AND SEDIMENT DEPOSITION. THE CONTRACTOR SHALL REMOVE ALL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS, INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS. THE CONTRACTOR SHALL RE-STABILIZE THE AREAS WHERE SEDIMENT REMOVAL RESULTS IN EXPOSED SOIL. REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN 7 DAYS OF DISCOVERY, UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL CONSTRAINTS. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AUTHORITIES AND OBTAIN ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK IN SURFACE WATERS

CONSTRUCTION SITE VEHICLE EXIT LOCATIONS SHALL BE INSPECTED DAILY FOR EVIDENCE OF SEDIMENT TRACKING ONTO PAVED SURFACES. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES WITHIN 24 HOURS OF DISCOVERY.

IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED IN A MANOR AND AT A FREQUENCY SUFFICIENT TO MINIMIZE OFF-SITE

EROSION PREVENTION BMP SUMMARY: SEE EROSION AND SEDIMENT CONTROL PLAN SHEET AND BID FORM FOR TYPE, LOCATION, AND QUANTITY OF EROSION PREVENTION BMPS.

SEDIMENT CONTROL BMP SUMMARY: SEE EROSION AND SEDIMENT CONTROL PLAN SHEETS AND BID FORM FOR TYPE, LOCATION, AND QUANTITY OF SEDIMENT CONTROL BMPS.

DEWATERING AND BASIN DRAINING ACTIVITIES:
THE CONTRACTOR IS RESPONSIBLE FOR ADHERING TO ALL DEWATERING AND SURFACE DRAINAGE

WATER FROM DEWATERING ACTIVITIES SHALL DISCHARGE TO A TEMPORARY AND/OR PERMANENT SEDIMENT BASIN

IF WATER CANNOT BE DISCHARGED TO A SEDIMENTATION BASIN, IT SHALL BE TREATED WITH OTHER APPROPRIATE BMPS, TO EFFECTIVELY REMOVE SEDIMENT.

DISCHARGE THAT CONTAINS OIL OR GREASE MUST BE TREATED WITH AN OIL-WATER SEPARATOR OR

WATER FROM DEWATERING SHALL BE DISCHARGED IN A MANNER THAN DOES NOT CAUSE NUISANCE CONDITIONS, EROSION, OR INUNDATION OF WETLANDS.

BACKWASH WATER USED FOR FILTERING SHALL BE HAULED AWAY FOR DISPOSAL, RETURNED TO THE BEGINNING OF TREATMENT PROCESS. OR INCORPORATED INTO THE SITE IN A MANNER THAT DOES NOT CAUSE EROSION. THE CONTRACTOR SHALL REPLACE AND CLEAN FILTER MEDIAS USED IN DEWATERING DEVICES WHEN REQUIRED TO MAINTAIN ADEQUATE FUNCTION.

POLLUTION PREVENTION MANAGEMENT MEASURES:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POLLUTION PREVENTION MANAGEMENT MEASURES.

ALL POLLUTION PREVENTION MEASURES ARE CONSIDERED INCIDENTAL TO THE MOBILIZATION BID ITEM.

THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER DISPOSAL, IN COMPLIANCE WITH MPCA DISPOSAL REQUIREMENTS. OF ALL HAZARDOUS MATERIALS, SOLID WASTE, AND PRODUCTS ON-SITE.

THE CONTRACTOR SHALL ENSURE BUILDING PRODUCTS THAT HAVE THE POTENTIAL TO LEAK POLLUTANTS ARE KEPT UNDER COVER TO PREVENT THE DISCHARGE OF POLLUTANTS

THE CONTRACTOR SHALL ENSURE PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS, TREATMENT CHEMICALS, AND LANDSCAPE MATERIALS ARE COVERED TO PREVENT THE DISCHARGE OF POLLUTANTS.

THE CONTRACTOR SHALL ENSURE HAZARDOUS MATERIALS AND TOXIC WASTE IS PROPERLY STORED IN SEALED CONTAINERS TO PREVENT SPILLS, LEAKS, OR OTHER DISCHARGE. STORAGE AND DISPOSAL OF HAZARDOUS WASTE OR HAZARDOUS MATERIALS MUST BE IN COMPLIANCE WITH MINN. R. CH. 7045 INCLUDING SECONDARY CONTAINMENT AS APPLICABLE.

THE CONTRACTOR SHALL ENSURE ASPHALT SUBSTANCES USED ON-SITE SHALL ARE APPLIED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.

THE CONTRACTOR SHALL ENSURE PAINT CONTAINERS AND CURING COMPOUNDS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT AND/OR CURING COMPOUNDS SHALL NOT BE DISCHARGED INTO THE STORM SEWER SYSTEM AND SHALL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURE'S INSTRUCTION

THE CONTRACTOR SHALL ENSURE SOLID WASTE BE STORED, COLLECTED AND DISPOSED OF PROPERLY IN COMPLIANCE WITH MINN. R. CH. 7035.

THE CONTRACTOR SHALL ENSURE POTABLE TOILETS ARE POSITIONED SO THAT THEY ARE SECURE AND WILL NOT BE TIPPED OR KNOCKED OVER. SANITARY WASTE MUST BE DISPOSED OF PROPERLY IN ACCORDANCE WITH MINN R CH 7041

THE CONTRACTOR SHALL MONITOR ALL VEHICLES ON-SITE FOR LEAKS AND RECEIVE REGULAR PREVENTION MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE

THE CONTRACTOR SHALL ENSURE WASHOUT WASTE MUST CONTACT THE GROUND AND BE PROPERLY DISPOSED OF IN COMPLIANCE WITH MPCA RULES.

THE CONTRACTOR SHALL INCLUDE SPILL KITS WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES SECONDARY CONTAINMENT MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR.

THE CONTRACTOR SHALL ENSURE SPILLS ARE CONTAINED AND CLEANED UP IMMEDIATELY UPON DISCOVERY. SPILLS LARGE ENOUGH TO REACH THE STORM WATER CONVEYANCE SYSTEM SHALL BE REPORTED TO THE MINNESOTA DUTY OFFICER AT 1 800 422 0798

176070 SEH Project ACB ACB

Rev.#

Rev.#

Date

Revision Issue Description





CONTAMINATION SCREENING CHECKLIST

This checklist addresses mobilization of contaminants by stormwater infiltration. See Part III.D of the Construction Stormwater permit for additional prohibitions.

If the site being investigated receives discharges from vehicle fueling or maintenance facilities, STOP -Infiltration is prohibited under the CSW permit

Box	Question	Criteria or check box
1	Is the project located in a well head protection area	
2	Is the project located in a Drinking Water Supply Management Area (DWSMA)	
3	Is the project located in a Karst area	
4	If any of the above are checked, what measures will be implemented to ensure protection of drinking water supply	
	Assess the site a	nd proposed location of the BMP
1		story of soil or groundwater contamination at levels of concern? If Yes, d to Box 2; if No, proceed to Box 3.
2	If the answer to Box 1 is yes, has the contaminated soil or groundwater been remediated to acceptable levels? NOTE: closure letters sent by the MPCA do not assure that a site is not contaminated. Click on the link in Cell E8 for more information. If yes, proceed to Box 3.	If no or unknown, Stop. There is sufficient information to suggest that contaminants may be mobilized by infiltration. For Construction Stormwater permittees, infiltration is prohibited when the infiltration system will be constructed in areas where high levels of contaminants in soil or groundwater will be mobilized by the infiltrating stormwater. SEE FOOTNOTE
3	• • •	ox in which the item occurs on the site with the proposed BMP?
4	Underground storage tank vent(s) or fill port(s)	
5	Monitoring well(s)	
6	Soil pile(s) covered with plastic sheeting or tarp(s)	
7	Staining of soil(s) and/or dead vegetation	
8	Unusual odor(s)	
9	Mismanaged drum(s) or chemical container(s)	
10	Excavation(s) that is/are not backfilled with clean material	
11	Presence of debris that may indicate presence of structure(s) or activity(ies) that could result in contamination	
12	Site is a confirmed stormwater hotspot	
13	Are there any potential sources identified (che	ecked) in Boxes 4 through 12? If Yes, proceed to Box 14; if no proceed to Box 15.
14	For all potential sources identified (checked) in Boxes 5 through 13, can adequate separation be achieved? If yes, proceed to Box 16.	If no, Stop. There is sufficient information to suggest that contaminants may be mobilized by infiltration. For Construction Stormwater permittees, infiltration is prohibited when the infiltration system will be constructed in areas where high levels of contaminants in soil or groundwater will be mobilized by the infiltrating stormwater. SEE FOOTNOTE
	Assessi	ng adjacent properties
15		which the item occurs within the influence zone of the site property. See neet (click on tab at bottom of this spreadsheet).
16	Known groundwater or soil contamination on adjacent property	
17	Underground storage tank vents or fill ports	
18	Monitoring wells	
19	Soil piles covered with plastic sheeting or tarps	
20	Staining of soils and/or dead vegetation	
21	Unusual odors	
22	Mismanaged drums or chemical containers Excavations that are not backfilled with clean	
24	Presence of debris that may indicate presence of structures or activities that could result in	
25	contamination Site is a confirmed stormwater hotspot	
26	Are any potential sources identified (checked) in Boxes 16 through 25? If yes, proceed to Box 27	If no, Stop - Infiltration is appropriate
27	For all potential sources identified (checked) in Boxes 16 through 25, can adequate separation be achieved? If no, proceed to Box 28.	If yes, Stop - Infiltration is appropriate
28	Construction Stormwater permittees, infiltrati	ation to suggest that contaminants may be mobilized by infiltration. For on is prohibited when the infiltration system will be constructed in areas or groundwater will be mobilized by the infiltrating stormwater. SEE FOOTNOTE

highly recommended. For more information, see Stormwater management guidelines for sites with on-site contamination or Stormwater management guidelines for sites with off-site contamination at

 $\overline{\text{http://stormwater.pca.state.mn.us/index.php/Stormwater_infiltration_and_contaminated_soils_and_groundwater.}$

Revision Issue Description 176070 Rev.# Date Rev.# ACB ACB



PERMIT TERMINATION CONDITIONS:
THE CONTRACTOR IS RESPONSIBLE FOR ENSURING FINAL STABILIZATION OF THE ENTIRE SITE.
PERMIT TERMINATION CONDITIONS INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

ALL EXPOSED SOILS HAVE BEEN UNIFORMLY STABILIZED WITH AT LEAST 70% VEGETATION COVERAGE.

PERMANENT STORM WATER MANAGEMENT SYSTEM(S) ARE CONSTRUCTED AND ARE OPERATING

ALL DRAINAGE DITCHES, PONDS, AND ALL STORM WATER CONVEYANCE SYSTEMS HAVE BEEN CLEARED OF SEDIMENT AND STABILIZED WITH PERMANENT COVER TO PRECLUDE EROSION. ALL TEMPORARY SYNTHETIC BMPS HAVE BEEN REMOVED AND PROPERLY DISPOSED OF. IN RESIDENTIAL CONSTRUCTION, INDIVIDUAL LOTS ARE CONSIDERED FINALLY STABILIZED IF THE STRUCTURE(S) ARE FINISHED AND TEMPORARY EROSION PROTECTION AND DOWNGRADIENT PERIMETER CONTROL HAS BEEN COMPLETED, THE RESIDENCE HAS BEEN SOLD TO THE HOMEOWNER, AND

THE HOMEOWNER HAS BEEN PROVIDED A "HOMEOWNER FACT SHEET" BY THE CONTRACTOR.


AGRICULTURAL LAND DISTURBED HAS BEEN RETURNED TO ITS PRECONSTRUCTION AGRICULTURAL USE.


ALL SOIL DISTURBING ACTIVITIES HAVE BEEN COMPLETED.

TRUNK HIGHWAY 246 TRAIL

STORM WATER POLLUTION PREVENTION PLAN

28





GENERAL INFORMATION


- 1. ALL DISTANCES ARE APPROXIMATE.
- 2. MAINTAIN MINIMUM 11' TRAVEL LANES THROUGHOUT CONSTRUCTION

- 1. ALL TEMPORARY SIGNS ARE REQUIRED TO BE CRASHWORTHY PER THE AASHTO MANUAL FOR ASSESSING SAFETY HARDWARE 2016 (MASH-2016). TEMPORARY SIGN STRUCTURES THAT ARE CRASHWORTHY UNDER THE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM REPORT 350 (NCHRP-350) MAY BE USED PROVIDED THE DEVICES WERE ACQUIRED BY THE CONTRACTOR PRIOR TO DECEMBER 31ST, 2019. THE MINNESOTA TYPE "C" AND "D" BRACED LEG U-CHANNEL (KNEE BRACE) SIGN SUPPORT IS NOT ALLOWED.
- 2. WHEN MULTIPLE GROUND MOUNTED SIGN STRUCTURES ARE PLACED ADJACENT TO EACH OTHER THERE SHOULD BE NO MORE THAN 2 POSTS WITHIN 84" OF EACH OTHER. WHEN THIS SPACING CAN NOT BE MAINTAINED, THEN SIGN STRUCTURES SHALL BE OFFSET, AND STAGGERED WITH A MINIMUM OF 4' BETWEEN SIGN STRUCTURES.
- WHEN A SIGN OR BARRICADE IS ORIENTED SUCH THAT VISIBILITY TO ROAD USERS INCLUDING BIKES AND PEDESTRIANS IS REDUCED ENOUGH TO CAUSE A HAZARD, DELINEATE THE SIGN/BARRICADE WITH APPROPRIATE
- TEMPORARY SIGNS SHALL BE PLACED SUCH THAT OBSTACLES DO NOT BLOCK THEM FROM BEING VIEWED BY APPROACHING ROAD USERS. OBSTACLES MAY INCLUDE, BUT ARE NOT LIMITED TO, LIGHT POLES, TREES, SIGNS, AND BUILDINGS.
- TEMPORARY SIGNS SHALL BE PLACED AND ORIENTED APPROXIMATELY AS SHOWN IN THE PLAN, AT RIGHT ANGLES TO DIRECTION OF FACING THE TRAFFIC THEY ARE INTENDED TO SERVE, UNLESS OTHERWISE SPECIFIED.
- LONGITUDINAL DROPOFFS SHALL BE SIGNED AS SHOWN IN THE "MINNESOTA TEMPORARY TRAFFIC CONTROL FIELD MANUAL" PAGES (6K-aj) THRU (6K-al) UNLESS OTHERWISE SPECIFIED IN THESE PLANS.

WATE OF DIFO						
"W" SERIES						
SIGN	SIGN NO.	COLOR	SIZE (IN.)			
	W1-4 (L,R)	BLACK ON ORANGE	36 X 36			
ROAD WORK AHEAD	W20-1	BLACK ON ORANGE	36 X 36			
LANES	W20-X17	BLACK ON ORANGE	36 X 36			
SHOULDER	W20-X5a	BLACK ON ORANGE	36 X 36			

"G" SERIES						
SIGN	SIGN NO.	COLOR	SIZE (IN.)			
END ROAD WORK	G20-2	BLACK ON ORANGE	36 X 18			

"R" SERIES						
SIGN	SIGN NO.	COLOR	SIZE (IN.)			
SIDEWALK CLOSED	R9-9	BLACK ON WHITE	24 X 12			
TRAIL CLOSED	R9-9 W/ OVERLAY	BLACK ON WHITE	24 X 12 20 X 5			
SIDEWALK OLOSED AFEAD CROSS HERE	R9-11R	BLACK ON WHITE	24 X 12			



SIGN ASSEMBLY

176070

ACB

ACB

Rev.#


BARRICADE ASSEMBLY

TRAFFIC FLOW ARROW

CHANNELIZING DEVICE (25' SPACING)




SEH Project






GENERAL NOTES:

1. CONTRACTOR TO PLACE
ADEQUATE NUMBER OF
BARRICADES TO CLOSE THE
ROAD WHERE APPLICABLE.
BARRICADES SHALL BE IN
ACCORDANCE WITH THE MUTCD.



TRUNK HIGHWAY 246 TRAIL
NORTHFIELD, MINNESOTA

PHASE 1
TRAFFIC CONTROL LAYOUT



176070

ACB


ACB

Rev.#

Date

Rev.#





ACB

ACB

90% PLANS

TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA

SIGNING DETAILS

of 42

SP 6614-33

PERMANENT PAVEMENT MARKING PLAN

NOTES & GUIDELINES

NOTES & GUIDELINES

GENERAL INFORMATION:

- 1. EDGE LINES AND LANE LINES ARE TO BE BROKEN ONLY AT INTERSECTIONS WITH PUBLIC ROADS, AND AT PRIVATE ENTRANCES IF THEY ARE CONTROLLED BY AN AGENCY PLACED YIELD SIGN, STOP SIGN OR TRAFFIC SIGNAL. THE BREAK POINT IS TO BE AT THE START OF THE MAINLINE RADIUS.
- 2. DO NOT APPLY THE PAVEMENT MARKINGS WHEN WEATHER AND OTHER CONDITIONS CAUSE A FILM OF DUST OR DEBRIS TO BE DEPOSITED ON THE PAVEMENT SURFACE AFTER CLEANING AND BEFORE THE MARKING MATERIAL IS APPLIED.
- 3. THE FILLING OF TANKS, POURING OF MATERIALS OR CLEANING OF EQUIPMENT SHALL NOT BE PERFORMED ON UNPROTECTED PAVEMENT SURFACES UNLESS ADEQUATE PROVISIONS ARE MADE TO PREVENT SPILLAGE OF MATERIAL.

PERMANENT PAVEMENT MARKING PLAN INDEX

- 35 PERMANENT PAVEMENT MARKING TITLE SHEET
- PERMANENT PAVEMENT MARKING TABULATIONS INTERIM PAVEMENT MARKINGS
- N/A DETAILS
- 5-6 TYPICALS

STRIPING KEY

CIRCLE-MULTI-COMPONENT

1ST DIGIT WIDTH

2ND DIGIT PATTERN

3RD DIGIT COLOR W - WHITE - SOLID - BROKEN

Y - YELLOW T — DOTTED
D — DOUBLE SOLID
K — DOUBLE BROKEN
H — DOUBLE DOTTED B - BLACK

G=GROUND IN W=WET REFLECTIVE C=CONTRAST E=ENHANCED SKID RESISTANCE

EXAMPLE: (4SW)

=4" SOLID LINE WHITE PREF THERMO

PERMANENT PAVEMENT MARKING TITLE SHEET

SP 6614-33

SEH Project

176070

ACB

ACB

Rev.#

Date

Rev.#


Revision Issue Description





TRUNK HIGHWAY 246 TRAIL NORTHFIELD, MINNESOTA


STRIPING DETAILS


35

















TH 246 TRAIL STA:12+00 - STA: 12+95

Sheet No. 42 Of 42 Sheets