


NORTH

	= Catch Basin
C	= Cable TV
C&G	= Curb and Gutter
CHL	= Chainlink Fence
CO	= Clean Out
COC	= Center of Channel
CMP	= Corrugated Metal Pipe
CS	= Curb Stop
CI	= Cast Iron
CW	= Concrete Sidewalk
DWY	= Driveway
E	= Electric
	= Electric Meter
EV	= Electric Vault
	= Fire hydrant
G	= Gas Main
	= Gas Meter
	= Guy Anchor
IE	= Invert Elevation
	= Light Pole
OH	= Overhead
(P)	= Painted Utility Location
PVC	= Polyvinyl Chloride
	= Power Pole
	= Power Pole with luminaire
(R)	= Record Utility Location
RCP	= Reinforced Concrete Pipe
	= Sanitary Manhole
	= Storm Manhole
	= Telephone Pedestal
T	= Telephone
	= Traffic flow direction
	= Traffic arrow painted on ground
UG	= Underground
VCP	= Vitrified Clay Pipe
	= Water Main Valve
	= Water Manhole
W	= Water Main
	= Deciduous Tree
	= Coniferous Tree
	= Surface Water Flow Direction



The map shows a grid of streets in Northfield, MN. Key streets include Highway 100 (Dodge St), Highway 13 (Hwy 13), and Highway 169 (Hwy 169). The project location is marked with a black dot at the intersection of Highway 100 and Highway 13. A line connects this dot to a star on a map of Minnesota, which is labeled 'NORTHFIELD'.

<u>SHEET</u>	<u>SUBJECT</u>
1	TITLE SHEET & LOCATION MAP
2-4	SWPPP NOTES & DETAILS
5-15	DETAILS
16-18	GRADING PLAN
19-24	PLAN AND PROFILES

SPECIFICATIONS WHICH APPLY

ALL CONSTRUCTION AND MATERIALS SHALL COMPLY WITH THE MOST RECENT EDITION OF MNDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION, INCLUDING PUBLISHED TECHNICAL MEMORANDA, MINNESOTA PLUMBING CODE, AND WITH THE CITY ENGINEERING STANDARD SPECIFICATIONS FOR WATERMAIN & SERVICE LINE, SANITARY SEWER AND STORM SEWER INSTALLATION (PER "STANDARD UTILITIES SPECIFICATIONS" BY THE CITY ENGINEERS ASSOCIATION OF MINNESOTA), AND THE CITY'S STANDARD DETAILS AND SPECIFICATIONS.

GENERAL NOTES

1. CONTRACTOR AND ALL SUBCONTRACTORS SHALL COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES GOVERNED BY STATE AND LOCAL JURISDICTION.
2. COORDINATE ELECTRIC, GAS & TELEPHONE UTILITY INSTALLATION & ROUTING WITH LOCAL UTILITY COMPANIES
3. ANY ALTERATIONS OR REVISIONS TO THE SITE DEVELOPMENT PLAN AS SHOWN SHALL NOT BE THE RESPONSIBILITY OF JONES, HAUGH & SMITH INC. AND SHALL RELEASE JONES, HAUGH & SMITH INC. OF ANY LIABILITY FOR ANY DAMAGES CAUSED THEREAS UNLESS WRITTEN AUTHORIZATION OR PLAN REVISION HAS BE APPROVED BY JONES, HAUGH & SMITH INC. PRIOR.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FOR CONSTRUCTION.
5. LANDSCAPING, IRRIGATION, AND LIGHTING NOT A PART OF THIS PLAN.

SWPPP GENERAL NOTES

1. THIS PLAN IS MEANT AND PROVIDED AS A GUIDE IN THE PROVISION OF SEDIMENT AND EROSION CONTROL (ESC) BMP'S AS REQUIRED BY THE NPDES PERMIT.
2. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES, ALTHOUGH NOT SHOWN HERE, MAY BE REQUIRED TO COMPLY WITH THE PROVISIONS OF THE PERMIT.
3. PROVISION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL BMP'S IN ACCORDANCE WITH THE NPDES PERMIT IS THE RESPONSIBILITY OF THE CONTRACTOR, REGARDLESS OF WHAT IS SHOWN ON THIS PLAN.
4. MAINTENANCE OF ESC BMP'S IS INCIDENTAL TO THE WORK.
5. NO ADDITIONAL PAYMENT WILL BE MADE FOR ADDITIONAL EROSION CONTROL BMP'S AS REQUIRED BY THE NPDES PERMIT.
6. THE CONTRACTOR SHALL OBTAIN THE NPDES PERMIT FROM THE MPCA AND PAY ANY APPLICABLE FEES AS WORK INCIDENTAL TO THE CONTRACT.
7. SHOULD MPCA ENFORCEMENT ACTIONS OCCUR, THE CONTRACTOR WILL BE THE CO-PERMITTEE RESPONSIBLE FOR CORRESPONDING WITH THE MPCA.
8. THE CONTRACTOR WILL BE PAY ALL FINES IMPOSED BY REGULATING AUTHORITIES DUE TO NON-COMPLIANCE WITH THE TERMS OF THE NPDES PERMIT WITH NO COST TO THE OWNER.

BENCHMARK:

TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

DESIGN ENGINEER:

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JOHN H. SCHULTE V, PE LICENSE NO. 44639

DATED:

The subsurface utility information in this plan is Utility Quality Level D. This Utility Quality Level was determined according to the guidelines of CII/ASCE 38-02, entitled "Standard Guidelines for the collection and depiction of existing subsurface utility data."

Some site improvements and topography may have been concealed by winter conditions at the time of survey.



COPYRIGHT
by JONES, HAUGH & SMITH INC
This drawing and format are protected by
Copyright and all rights are reserved. The use
of this drawing and format is strictly prohibited
without the written consent and permission of
Jones, Haugh & Smith Inc.

No responsibility is accepted for the locations of utilities shown hereon. Verification of actual locations should be requested prior to the commencement of construction or the taking of any other action relying on the actual locations.

GOPHER STATE ONE-CALL: 1-800-252-1166

REV.	BY	DATE
-	-	-



415 West North Street Owatonna, MN 507-451-4598

DESIGNED:	JHS5
DRAWN:	JHS5
CHECKED:	BJJ
Date:	5/14/26
DWG:	23-259

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
TITLE SHEET

SHEET
OF
24

CONSTRUCTION ACTIVITY INFORMATION

PROJECT NAME: HARVEST HILLS SECOND ADDITION
PROJECT LOCATION:
SECTION: SE 1/4 SECTION 12-T111-R20W
CITY: NORTHFIELD
TOWNSHIP: BRIDGEWATER
COUNTY: RICE

PROJECT SIZE: 10.10 DISTURBED ACRES

PROJECT TYPE: RESIDENTIAL SUBDIVISION

MAJOR SOIL TYPES:
1. 1410B, RACINE SILT LOAM

IMPERVIOUS SURFACE:
EXISTING: 0.00 AC
PROPOSED: 4.54 AC
DIRECT DISCHARGE FROM IMPERVIOUS SURFACE: 0.38 AC

RECEIVING WATERS: CITY OF NORTHFIELD STORM SEWER SYSTEM

DATES OF CONSTRUCTION: SPRING 2026-FALL 2027

OWNER: UNDERGROUND UTILITY CONTRACTOR:
SCHROM CONSTRUCTION TBD
NICK KRAFT
1116 N. RIVERFRONT DR
MANKATO, MN 56001
PHONE 507-257-5110

PARTY RESPONSIBLE FOR LONG TERM O&M: OWNER

GENERAL SITE INFORMATION

THIS SITE TREATS STORMWATER VIA A A PERMANENT STORMWATER POND. THE SITE'S STORMWATER POND OR TEMPORARY SEDIMENT BASINS WILL BE PART OF THE FIRST GRADING ACTIVITIES PERFORMED AT THE SITE. THE POND WILL NOT BE DIRECTLY CONNECTED TO ITS OUTLET UNTIL ALL UPSTREAM FEATURES ARE FULLY STABILIZED. PUMPING WILL BE UTILIZED IN THE INTERIM.

IMMEDIATELY FOLLOWING GRADING OF SLOPES OF 3:1 OR GREATER WHICH DRAIN TO WATERS OF THE STATE, SLOPES WILL BE STABILIZED WITH EROSION BLANKET OR HYDROSEEDING OVER A MINIMUM OF 6" OF TOPSOIL.

ALL EROSION CONTROL MEASURES SHALL REMAIN IN PLACE AND BE MAINTAINED IN GOOD CONDITION UNTIL THE SITE HAS BEEN RE-VEGETATED. THE CONTRACTOR MAY REMOVE NECESSARY SILT FENCING TO CONSTRUCT ROADWAYS WHILE MAINTAINING ADEQUATE EROSION CONTROL IN ADJACENT AREAS.

SUFFICIENT TOPSOIL SHALL BE STOCKPILED TO ALLOW FOR THE REPLACEMENT OF A MINIMUM OF 6" OF TOPSOIL FOR DISTURBED AREAS TO BE RE-VEGETATED. STOCKPILES WILL BE STABILIZED WITH TARPS OR SEEDED WITH OATS OR WINTER WHEAT WITHIN 7 DAYS OF COMPLETION, WITH SILT FENCE RINGS IN PLACE PRIOR TO STOCKPILE CONSTRUCTION.

CONTRACTOR WILL SCHEDULE SITE GRADING, UTILITY INSTALLATION, AND GRAVEL SURFACE CONSTRUCTION SO THAT THE GENERAL SITE CAN BE MULCHED AND RE-SEEDED SOON AFTER DISTURBANCE.

DISTURBED AREAS SHALL BE STABILIZED WITHIN 7 DAYS OF CESSATION OF DISTURBANCE. STABILIZATION ACTIVITIES WILL BEGIN IMMEDIATELY AND BE COMPLETED WITHIN 7 DAYS. STABILIZATION WILL BE COMPLETED WITHIN 7 DAYS FOR SLOPES 3:1 AND STEEPER OR WHEN IDENTIFIED AS IMPAIRED.

SILT FENCES WILL BE CHECKED AFTER EACH RAIN EVENT AND DAILY DURING A PROLONGED RAINFALL. IMMEDIATELY REPAIR FAILED OR FAILING MEASURES AND REPORT IN LOG BOOK. REMOVE SEDIMENT DEPOSITS FROM SILT FENCE AND BALE CHECKS WHEN SEDIMENT REACHES APPROXIMATELY 1/2 THE HEIGHT OF THE BARRIER.

BARRIERS WILL BE REPLACED WHEN THEY DECOMPOSE OR BECOME INEFFECTIVE BEFORE THE BARRIERS ARE NO LONGER NECESSARY. ANY SEDIMENT REMAINING IN-PLACE AFTER THE BARRIERS ARE NO LONGER NECESSARY WILL BE DRESSED TO CONFORM TO EXISTING GRADE, AND PREPARED AND SEEDED WITH THE APPROPRIATE SEED MIX, AS DIRECTED BY THE ENGINEER.

IN THOSE AREAS WHERE WOOD FIBER BLANKET OR OTHER SLOPE STABILIZATION METHODS HAVE FAILED, THE SLOPE SHALL BE REESTABLISHED, SEED AND TOPSOIL REPLACED, AND ADDITIONAL SLOPE TREATMENT INSTALLED AS DIRECTED BY THE ENGINEER.

BARRIERS WILL BE REMOVED WHEN FINAL STABILIZATION OF THE SLOPES HAS BEEN COMPLETED AS DETERMINED BY THE ENGINEER.

NO STORMWATER MITIGATION MEASURES WERE REQUIRED AS A PART OF ENVIRONMENTAL, ARCHAEOLOGICAL OR OTHER REQUIRED LOCAL, STATE, OR FEDERAL REVIEW OF THIS PROJECT.

THIS PROJECT IS NOT LOCATED IN A KARST AREA NECESSITATING MEASURES TO PROTECT DRINKING WATER SUPPLY.

EROSION PREVENTION PRACTICES

APPROPRIATE CONSTRUCTION PRACTICES WILL BE USED TO MINIMIZE EROSION. AREAS OF NON-DISTURBANCE WILL BE DELINEATED (FLAGGED, ETC.) ON THE SITE BEFORE WORK BEGINS.

CONTRACTOR SHALL PHASE CONSTRUCTION, MAINTAIN VEGETATIVE BUFFER STRIPS, AND PROVIDE HORIZONTAL SLOPE STAKING IN ORDER TO MINIMIZE EROSION. SUGGESTED CONSTRUCTION SEQUENCING TO MINIMIZE EXPOSED AREAS SUBJECT TO EROSION HAS BEEN SHOWN, BUT ULTIMATE SEQUENCING IS UP TO THE CONTRACTOR. THE SWPPP ON-SITE WILL BE RED-LINED BY THE CONTRACTOR TO INDICATE FINAL SEQUENCING.

DOWNSTREAM SILT FENCE AND INLET PROTECTION DEVICES WILL BE INSTALLED PRIOR TO EARTH MOVING ACTIVITIES.

SLOPES SHALL BE "CAT-TRACKED" WHEN COMPLETE SUCH THAT THE TRACK DEPRESSIONS ARE PERPENDICULAR TO DRAINAGE FLOW.

SILT FENCE SHALL BE INSTALLED BEFORE WORK BEGINS. SILT FENCE LIMITS SHALL COINCIDE WITH DOWNGRADE GRADING LIMITS UNLESS OTHERWISE NOTED.

SILT FENCE USED ON SLOPES SHALL BE PLACED SUCH THAT 100 LINEAL FEET OF SILT FENCE STABILIZES APPROXIMATELY 0.25 ACRES OF DRAINAGE.

THE WETTED PERIMETER OF DRAINAGE SWALES WILL BE STABILIZED WITH RAPID STABILIZATION MEASURES WITHIN 200' OF THE SITE BOUNDARY LINE WITHIN 24 HOURS.

PIPE OUTLETS WILL BE PROVIDED WITH ENERGY DISSIPATION (RIP RAP) WITHIN 24 HOURS OF CONNECTION TO WATERS OF THE STATE.

IF NOT SHOWN ON THE PLAN: ALL EXPOSED SOIL AREAS WITHIN 200' OF SURFACE WATER OR A STORMWATER CONVEYANCE WHICH HAVE CONTINUOUS POSITIVE SLOPES WILL HAVE TEMPORARY EROSION PROTECTION OR PERMANENT COVER FOR THE EXPOSED SOILS YEAR-ROUND, ACCORDING TO THE FOLLOWING TABLE OF SLOPES AND TIME FRAMES:

GRADE OF SLOPE	TIME (MAX.)	BMP
STEEPER THAN 3:1	7 DAYS	RAPID STABILIZATION METHOD 4
4:1 TO 3:1	7 DAYS	RAPID STABILIZATION METHOD 2
FLATTER THAN 4:1	7 DAYS	TYPE 1 DISC ANCHORED MULCH

STABILIZATION WILL COMMENCE IMMEDIATELY UPON COMPLETION OF GRADING AND BE COMPLETE WITHIN THE STATED TIMEFRAME UNLESS FURTHER GRADING ACTIVITIES WILL COMMENCE PRIOR TO COMPLETION DATE. FROZEN GROUND IS CONSIDERED STABILIZED.

CUT AREAS WHERE NO GRADING HAS OCCURRED WITHIN 7 DAYS WILL BE STABILIZED USING BIO-ROLLS A MINIMUM OF EVERY 20 LINEAL FEET IN ORDER TO PREVENT EROSION.

FILL SLOPES WHICH DRAIN TO WATERS OF THE STATE OR OFFSITE SHALL BE STABILIZED IMMEDIATELY UPON CESSATION OF GRADING ACTIVITIES. THUS, IF SLOPES ARE BROUGHT TO SUBGRADE ELEVATION AND WILL CEASED BEING WORKED ON UNTIL TOPSOIL RE-SPREADING, THEY WILL BE STABILIZED IN THE INTERIM. STABILIZE SLOPES WITH INTERIM LIMES OF SILT FENCE OR BIO-ROLLS EVERY 20 LINEAL FEET.

SOIL STOCKPILES WHICH REMAIN UNWORKED FOR MORE THAN 7 DAYS WILL BE STABILIZED WITH SEED AND MULCH OR TARPS WITH SILT FENCE RINGS IN PLACE PRIOR TO STOCKPILE CONSTRUCTION. DO NOT LOCATE STOCKPILES IN BUFFERS OR SURFACE WATERS.

IF THIS PROJECT IS SUBJECT TO A DNR WORK IN WATERS RESTRICTIONS. DURING FISH SPAWNING TIMES, EXPOSED SOIL AREAS MUST BE STABILIZED WITHIN 24 HOURS DURING THE SPAWNING PERIOD.

THE WETTED PERIMETER OF THE LAST 200' OF DRAINAGE SWALES WILL BE STABILIZED WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER OR PROPERTY LINE. DO NOT USE MULCH, TACKIFIER OR SIMILAR EROSION PREVENTION MEASURES IF THE SLOPES OF SWALES ARE GREATER THAN 2%.

SEDIMENT CONTROL PRACTICES

CONTRACTOR SHALL FURNISH, INSTALL, AND MAINTAIN: SEDIMENT CONTROLS FOR TEMPORARY AND PERMANENT DRAINAGE BASINS AND DRAINAGE DITCHES THAT ARE A PART OF THIS DESIGN, AND UPGRADIENT OF ANY BUFFER ZONES, INCLUDING:

- CHECK DAMS AND/OR WOOD FIBER BLANKETS TO ENSURE SHEET FLOW AND PREVENT RILLS FOR SLOPE LENGTHS GREATER THAN 75' WITH A SLOPE OF 3:1 OR GREATER (SEE NOTES ON BIO-ROLLS SPACED EVERY 20' ABOVE)
- SILT FENCE AT ALL DOWN GRADIENT PERIMETERS INSTALLED PRIOR TO ALL LAND DISTURBING ACTIVITIES
- INLET PROTECTION AT ALL DRAIN INLETS INCLUDING NEWLY CONSTRUCTED CATCH BASINS, INCLUDING CATCH BASIN STRUCTURES PRIOR TO CASTING INSTALLATION, AND SANITARY SEWER STRUCTURES.
- SILT FENCING AROUND TEMPORARY SOIL STOCKPILES
- ROCK OR WOOD CHIP CONSTRUCTION SITE ENTRANCES
- DAILY STREET SWEEPING OF TRACKED SEDIMENT ONTO PAVED SURFACES
- CONCRETE TRUCKS SHALL PERFORM WASHOUT ACTIVITIES OFFSITE

TYPICALLY, UTILIZE THE PERMANENT STORMWATER PONDS FOR TEMPORARY SEDIMENTATION. IF AN AREA GREATER THAN 5 ACRES IS DESIGNED TO EVENTUALLY DRAIN TO A FILTRATION OR INFILTRATION BASIN, CONSTRUCT A TEMPORARY SEDIMENTATION BASIN UPSTREAM OF ULTIMATE BASIN. CLEAN OUT TEMPORARY BASINS WHEN SEDIMENT DEPTH REACHES 1/2 VOLUME WITHIN 72 HOURS OF DISCOVERY.

IF SURFACE WATER IS TO DISCHARGE OFFSITE BEFORE TREATMENT, DIRECT TO VEGETATED AREAS.

DEWATERING AND BASIN DRAINING

CONTRACTOR SHALL PROVIDE PERMITS FOR ALL DEWATERING ACTIVITIES (INCIDENTAL TO CONSTRUCTION)
ALL DEWATERING ACTIVITIES SHALL DISCHARGE TO A TEMPORARY SEDIMENTATION BASIN OR DEWATERING BASIN CONSTRUCTED NEAR OR PART OF THE PERMANENT STORMWATER BASIN.

THE DEWATERING OR TEMPORARY SEDIMENT BASINS WILL BE PUMPED THROUGH A FILTRATION SYSTEM CONSTRUCTED BY THE CONTRACTOR PRIOR TO DISCHARGE. NO BACKWASHING OF FILTERS ON-SITE.

DEWATERING CHANNELS WHICH ARE OVER LAND SHALL BE PROTECTED FROM EROSION. PLACE END OF HOSE ON FABRIC OR PLASTIC TO PREVENT EROSION.

CLEAN OUT TEMPORARY SEDIMENT BASINS TO DESIGN VOLUME AFTER SEDIMENT REACHES 1/2 DESIGN VOLUME.

CONSTRUCT DEWATERING ACTIVITIES SUCH THAT THEY WILL NOT CAUSE NUISANCE CONDITIONS, EROSION IN RECEIVING CHANNELS OR ON DOWN SLOPE PROPERTIES OR ADVERSELY AFFECT WETLANDS.

ADDITIONAL BMP'S FOR SPECIAL WATERS

THIS PROJECT DOES NOT DISCHARGE TO SPECIAL WATERS OR HAVE SIGNIFICANT IMPACTS TO WETLANDS

ADDITIONAL MEASURES HAVE BEEN INCLUDED AS RELATED TO IMPAIRMENTS OF THE CANNON RIVER WHICH IS WITHIN 1 MILE OF THE DISCHARGE POINT. ITEMS 23.9, 23.10 AND 23.11 OF THE NPDES GENERAL STORMWATER PERMIT ARE INCLUDED.

INSPECTIONS AND MAINTENANCE

CONTRACTOR SHALL INSPECT AND MAINTAIN MEASURES AT MINIMUM ONCE EVERY (7) DAYS DURING ACTIVE CONSTRUCTION, AND WITHIN 24 HOURS AFTER A RAINFALL EVENT OF 0.5" IN 24 HOURS. ALSO INSPECT AREAS ADJACENT TO THE SITE FOR ROGUE EROSION OR SEDIMENT.

DEWATERING DISCHARGE POINTS WILL BE PHOTOGRAPHED DAILY WITH RECORDS MAINTAINED IF DISCHARGE REACHES A SURFACE WATER.

INSPECTIONS WILL INCLUDE STABILIZED AREAS, EROSION PREVENTION AND SEDIMENT CONTROLS, AGGREGATE SURFACES, DISCHARGE CHANNELS AND DEVICES, PERMANENT STORMWATER BMP'S AND RECEIVING STORM SEWER FACILITIES.

STABILIZED AREAS WILL BE INSPECTED ONCE PER MONTH. WHERE WORK HAS BEEN SUSPENDED DUE TO FROZEN GROUND CONDITIONS, INSPECTIONS AND MAINTENANCE WILL TAKE PLACE AS SOON AS FINAL RUNOFF OCCURS AT THE SITE OR PRIOR TO RESUMING CONSTRUCTION, WHICHEVER COMES FIRST.

CONSTRUCTION SITE VEHICLE ENTRANCES WILL BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT BEING TRACKED ONTO PAVED SURFACES DAILY. TRACKED SEDIMENT MUST BE REMOVED FROM ALL OFF-SITE PAVED SURFACES WITHIN 24 HOURS OF DISCOVERY.

THE INSPECTION LOG MUST INCLUDE THE: DATE AND TIME, NAME OF INSPECTOR, FINDINGS INCLUDING SPECIFIC LOCATIONS OF CORRECTIONS REQUIRED, CORRECTIVE ACTIONS TAKEN WITH DATE AND TIME, RAINFALL AMOUNTS AND DATES VIA RAIN GAUGE OR WEATHER STATION WITHIN 1 MILE, DOCUMENTATION OF SEDIMENT DISCHARGE FROM SITE WITH PHOTOGRAPHS.

REPAIR ALL NONFUNCTIONAL BMP'S BY THE END OF THE NEXT BUSINESS DAY OR AS SOON AS FIELD CONDITIONS ALLOW.

RECORDS RETENTION

CONTRACTOR SHALL MAINTAIN RECORDS OF THE SEDIMENT RETENTION PROCEDURES ON-SITE. RECORDS WILL INCLUDE:
COPY OF THE SWPPP AND ANY CHANGES
INSPECTION AND MAINTENANCE RECORDS
PERMANENT OPERATION AND MAINTENANCE AGREEMENTS
CALCULATIONS FOR THE DESIGN OF TEMPORARY AND PERMANENT STORMWATER MANAGEMENT SYSTEMS

POLLUTION PREVENTION MANAGEMENT MEASURES

SOLID WASTE:
COLLECTED SEDIMENT, ASPHALT AND CONCRETE MILLINGS, FLOATING DEBRIS, PAPER, PLASTIC, FABRIC, CONSTRUCTION AND DEMOLITION DEBRIS AND OTHER WASTES MUST BE DISPOSED OF PROPERLY AND MUST COMPLY WITH MPCA DISPOSAL REQUIREMENTS. SIGNED SEPARATE DISPOSAL BINS WITH A SIGN REQUIRING USE OF SAID BINS WILL BE INSTALLED AND UTILIZED.

CONCRETE AND OTHER WASHOUTS:
PERFORM ALL CONCRETE TRUCK WASHOUTS OFFSITE.

SOLID AND LIQUID WASHOUT WASTE FROM OTHER MATERIALS (STUCCO, PAINT, FORM RELEASE OILS CURING COMPOUNDS ETC.) WILL BE DISPOSED OF IN A PROPERLY DESIGNATED LANDFILL.

PERFORM ALL HANDTOOLS WASHOUTS IN A LEAKPROOF CONTAINMENT FACILITY OR IMPERMEABLE LINER THAT PREVENTS RUNOFF ONTO ADJACENT SOILS. DEBRIS/SEDIMENT WILL NOT CONTACT THE GROUND SURFACE. A SIGN REQUIRING USE OF PROPER WASHOUT FACILITIES WILL BE INSTALLED ADJACENT TO SAID FACILITIES.

HAZARDOUS MATERIALS:
OIL, GASOLINE, PAINT AND ANY HAZARDOUS SUBSTANCES WILL BEE PROPERLY STORED, INCLUDING SECONDARY CONTAINMENT TO PREVENT SPILLS, LEAKS, OR OTHER DISCHARGE. RESTRICTED ACCESS TO STORAGE AREAS WILL BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE WILL BE IN COMPLIANCE WITH MPCA REGULATIONS. PLASTIC SHEETING UNDER AN ABSORBENT MATERIAL WILL BE PLACED ON THE GROUND NEAR FUEL STORAGE TANKS TO PREVENT SPILLS WHEN LOADING OR UNLOADING THE TANKS. SPILL KITS WILL BE PROVIDED NEAR STORAGE.

EXTERNAL WASHING OF TRUCKS AND OTHER CONSTRUCTION VEHICLES IS NOT ALLOWED ON-SITE. NO ENGINE DEGREASING IS ALLOWED ON SITE.

NO FLOCCULENTS ARE BEING UTILIZED TO ENHANCE SEDIMENTATION IN RETENTION FACILITIES.

PORTABLE TOILETS WILL BE SECURED.

SWPPP IMPLEMENTATION CHAIN OF RESPONSIBILITY

THE GENERAL CONTRACTOR SHALL PROVIDE A TRAINED, CERTIFIED, KNOWLEDGEABLE PERSON WHO SHALL SERVE AS THE SITE'S EROSION CONTROL INSPECTOR. THIS PERSON SHALL BE RESPONSIBLE FOR INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENT CONTROL BMP'S, AND SHALL MAINTAIN THE INSPECTION LOG AT THE PROJECT SITE.

EACH SUBCONTRACTOR ON-SITE WILL DESIGNATE AN EMPLOYEE AS ITS PROJECT SWPPP OFFICER. A LIST OF THESE OFFICERS WITH CONTACT INFORMATION WILL BE AVAILABLE ON-SITE. IT WILL BE SOLELY THE SWPPP OFFICERS' RESPONSIBILITY TO ENSURE THAT ALL ON-SITE ACTIVITIES PERFORMED BY ITS COMPANY COMPLY WITH THE SWPPP. THE GENERAL CONTRACTOR'S SWPPP INSPECTOR WILL HAVE AUTHORITY OVER ALL SUBCONTRACTOR'S SWPPP OFFICERS FOR WORK PERTAINING TO COMPLIANCE.

NOTE THE PERSONS RESPONSIBLE FOR EACH CONTRACTOR IN THE SWPPP.

SHOULD A SWPPP OFFICER FAIL TO ENSURE COMPLIANCE, THAT OFFICER'S FOREMAN OR DIRECT SUPERVISOR WILL ASSUME ALL RESPONSIBILITY.

SHOULD A SUBCONTRACTOR FAIL TO COMPLY WITH THE SWPPP, THE GENERAL CONTRACTOR WILL ASSUME ALL RESPONSIBILITY FOR COMPLIANCE.

SHOULD THE GENERAL CONTRACTOR FAIL TO COMPLY WITH THE SWPPP, THE OWNER WILL ASSUME ALL RESPONSIBILITY FOR COMPLIANCE.

SWPPP AMENDMENTS

THE CONTRACTOR IS RESPONSIBLE FOR DOCUMENTING CHANGES TO THE SWPPP VIA MARKUPS ON THE ON-SITE SWPPP DOCUMENTS. SHOULD ADDITIONAL MEASURES BE NEEDED BEYOND THE CAPABILITY OF THE CONTRACTOR, THE CONTRACTOR WILL CONTACT THE SWPPP DESIGNER FOR ASSISTANCE.

PERMIT TERMINATION CONDITIONS

THE CONTRACTOR WILL BE A CO-PERMITTEE DURING THE CONSTRUCTION OF THE PROJECT. AFTER DESIGNATED SURFACING OF THE PROJECT HAS BEEN COMPLETED, FOR PERMANENT VEGETATIVE COVER HAS BEEN ESTABLISHED OVER THE PERVIOUS AREAS OF THE SITE, THE PERMANENT STORMWATER TREATMENT FACILITIES ARE OPERATING AS DESIGNED AND HAVE BEEN RETURNED TO DESIGN CAPACITY, ANY SEDIMENT HAS BEEN REMOVED FROM STORMWATER CHANNELS, TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES HAVE BEEN REMOVED, DATED PHOTOGRAPHS OF THE SITE SHOWING FINAL STABILIZATION HAVE BEEN SUBMITTED TO THE OWNER, THE OWNER WILL, WITHIN 30 DAYS, SUBMIT THE NOTICE OF TERMINATION (NOT) AND DATED PHOTOGRAPHS TO THE MPCA.

NOTIFICATION OF THE MPCA IN CASE OF POLLUTION

IT IS THE DUTY OF THE CONTRACTOR TO NOTIFY THE MPCA IMMEDIATELY OF ANY DISCHARGE, ACCIDENTAL OR OTHERWISE, OF ANY SUBSTANCE OR MATERIAL UNDER HIS CONTROL WHICH, IF NOT RECOVERED, MAY CAUSE POLLUTION OF WATERS OF THE STATE, AND THE CONTRACTOR SHALL RECOVER AS RAPIDLY AND THOROUGHLY AS POSSIBLE SUCH SUBSTANCE OR MATERIAL AND TAKE IMMEDIATELY SUCH OTHER ACTION AS MAY BE REASONABLY POSSIBLE TO MINIMIZE OR ABATE POLLUTION OF WATERS OF THE STATE CAUSED THEREBY.

SEDIMENT LEAVING THE CONSTRUCTION SITE AND ENTERING A PUBLIC WATER IS CAUSE FOR NOTIFICATION.

PETROLEUM SPILLS LARGER THAN 5 GALLONS MUST BE REPORTED.

MINNESOTA DUTY OFFICER: 800-422-0798

DISCUSSION OF INFILTRATION VIABILITY

SOILS AT THE SITE ARE GENERALLY POORLY DRAINED, RESULTING IN SEASONALLY SATURATED SOILS NEAR THE SURFACE. THIS ELEVATED WATER TABLE COMBINED WITH SITE GRADING REQUIREMENTS PRECLUDES INFILTRATION AS A METHOD OF STORMWATER TREATMENT AS IT IS INFEASIBLE TO OBTAIN 3' OF VERTICAL SEPARATION OF BETWEEN POTENTIAL TREATMENT DEVICES AND SEASONALLY SATURATED SOILS.

IRRIGATION IS PROPOSED AS A MEASURE OF VOLUME CONTROL.

QUALIFIED SWPPP PERSONNEL INFORMATION

CERTIFIED SWPPP DESIGNER:

JOHN H. SCHULTE V. PE
JONES HAUGH & SMITH, INC.
515 SOUTH WASHINGTON AVE
ALBERT LEA, MN 56007
(507) 451-4598

DATES OF LAST TRAINING: 1/5/24 Expires 2027
CONTENT: U of M DESIGN OF CONSTRUCTION SWPPP

CERTIFIED EROSION CONTROL SUPERVISOR:

NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____

DATES OF LAST TRAINING: _____

CONTENT: _____

CERTIFIED SWPPP INSTALLER:

NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____

DATES OF LAST TRAINING: _____

CONTENT: _____

CERTIFIED SWPPP INSPECTOR:

NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____

DATES OF LAST TRAINING: _____

CONTENT: _____

GRADING CONTRACTOR:

NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____

OTHER LAND DISTURBING CONTRACTOR:

NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____


OTHER LAND DISTURBING CONTRACTOR:


NAME: _____

FIRM: _____

ADDRESS: _____

PHONE: _____

	REV.	BY	DATE	REVISION DESCRIPTION	 JONES HAUGH SMITH Engineers + Surveyors 415 West North Street Owatonna, MN 56045-4598	DESIGNED: JHS	 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota. John H. Schulte V License No. 44639 Date: 5/14/26	HARVEST HILLS SECOND ADDITION SCHROM CONSTRUCTION OUTLOT A HARVEST HILLS SWPPP NARRATIVE	SHEET 2 OF 24
	-	-	-	-		DRAWN: JHS			
						CHECKED: BU			
						Date: 5/14/26			
						DWG: 23-259			



LEGEND

- 848 EXISTING ELEVATION CONTOUR LINE
- 848 PROPOSED ELEVATION CONTOUR LINE
- IP CATCH BASIN INLET PROTECTION
- CE CONSTRUCTION ENTRANCE
- SF SILT FENCE - MACHINE SLICED
- R4 RAPID STABILIZATION METHOD 4

TURF ESTABLISHMENT

- PROVIDE A MINIMUM OF 6" OF TOPSOIL OVER ALL AREAS DESIGNATED TO RECEIVE TURF.
- STABILIZE ALL OTHER DISTURBED AREAS OF THE SITE NOT SHOWN TO RECEIVE SPECIAL TREATMENT ON THIS PLAN IN ACCORDANCE WITH THE LANDSCAPE PLAN OF IF NOT SHOWN, WITH HYDROSEED MIXTURE AS MNDOT RAPID STABILIZATION METHOD 3 WITH:
SEED MIX 25-131 @ 100 LB/ACRE
FERTILIZER 22-5-10 @ 300 LBS/ACRE
TYPE 1 HYDRAULIC SOIL STABILIZER

WINTER STABILIZATION

- IN THE EVENT THAT FINAL STABILIZATION OF THE SITE HAS NOT OCCURRED PRIOR TO WINTER CONDITIONS, THE FOLLOWING ACTIVITIES WILL OCCUR:
- STABILIZE ALL AREAS DESIGNATED TO RECEIVE TURF WITH SODDING OR SEED MIX 22-112 @ 40 LB/ACRE WITH SEED MIX 21-112 (WINTER WHEAT) @ 100 LB/ACRE, AND TYPE 1 MULCH FROZEN TO GROUND WITH WATER
 - SPOT CHECK AND STABILIZE ALL AREAS ALREADY STABILIZED WITH THE ABOVE

REQUIRED BMP INSPECTION & MAINTENANCE SCHEDULE

Item	Frequency
PERIMETER SILT FENCE/BIO-ROLL	WEEKLY OR AFTER EACH 0.5" RAIN EVENT. CLEAN WHEN DEVICES REACH 50% CAPACITY
INLET PROTECTION	WEEKLY OR AFTER EACH 0.5" RAIN EVENT. CLEAN WHEN DEVICES REACH 50% CAPACITY
ROCK CONSTRUCTION ENTRANCE	WEEKLY OR AFTER EACH 0.5" RAIN EVENT
STREET SWEEPING	DAILY
PERMANENT STABILIZATION	WEEKLY OR AFTER EACH 0.5" RAIN EVENT UNTIL 100% OF STABILIZED AREA REACHES 70% COVERAGE



DRAWINGS ON 11x17 SHEETS ARE HALF SCALE

REV.	BY	DATE	REVISION DESCRIPTION



415 West North Street Owatonna, MN 56045-4598

DESIGNED: JHS
DRAWN: JHS
CHECKED: BJU
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
SWPPP & GRADING PLAN

SHEET
3
OF
24


SOILS MAP



1410B, RACINE SILT LOAM

PROJECT LOCATION

MAP OF SURFACE WATERS




0.98 MILES


PROJECT LOCATION

SPACING OF CHECKS:

$$\text{SPACING (FT)} = \frac{\text{HEIGHT OF CHECK (FT)} \times 100}{\text{DITCH GRADE (\%)}}$$




BIO-ROLL BLANKET AND/OR BIO-ROLL DITCH CHECK



- NOTES:
1. FILTER FABRIC SHALL BE PLACED UNDER ROCK TO STOP MIGRATION OF MUD THROUGH ROCK.
 2. ENTRANCE MUST BE REGULARLY MAINTAINED TO PREVENT SEDIMENTATION ON PUBLIC ROADWAYS. FUGITIVE ROCK WILL BE REMOVED FROM ADJACENT ROADWAYS DAILY OR MORE FREQUENTLY AS NECESSARY.

EROSION CONTROL PROTECTION AT CONSTRUCTION ACCESS




SPACING OF CHECKS:


$$\text{SPACING (FT)} = \frac{\text{HEIGHT OF CHECK (FT)} \times 100}{\text{DITCH GRADE (\%)}}$$

NOTE:
REMOVE SEDIMENT OR REPLACE FENCE
WHEN SEDIMENT REACHES 1/3 HEIGHT
OF FENCE

SILT FENCE DITCH CHECK



CATCH BASIN INLET PROTECTION



- NOTES:
1. PLACE BOTTOM EDGE OF FENCE INTO 6" DEEP
 2. POSTS SHALL BE 4" ON CENTER, 2" x 2" HARDWOOD, PINE OR STANDARD STEEL FENCE POSTS DRIVEN 2' INTO THE GROUND.
- ALTERNATE PERIMETER CONTROL METHODS, INCLUDING TOPSOIL BERMS WILL FOLLOW MNDOT SPECIFICATIONS INCLUDING:
- TOPSOIL
TOPSOIL EXCAVATION MATERIAL PER 2105, TRAPEZOID SHAPE WITH 7 FT. BASE WIDTH, MIN. HEIGHT 2 FT., AND 2:1 (V:H) SIDE SLOPES.

EROSION CONTROL FENCE
(MACHINE SLICED)

NOT TO SCALE

REV.	BY	DATE	REVISION DESCRIPTION

JONES HAUGH SMITH
Engineers + Surveyors
415 West North Street Owatonna, MN 56057
507-451-4598


DESIGNED: JHS
DRAWN: JHS
CHECKED: BJU
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.


John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
SWPPP DETAILS


SHEET
4
OF
24




DRIVEWAY SECTION AT SIDEWALK




CONCRETE WALK SECTION



TYPICAL SECTION
PRIVATE ROAD



TYPICAL SECTION
66' ROW



- NOTES:
1. SIDEWALK MAY BE ELIMINATED ON ONE OR BOTH SIDES OF THE STREET IN SOME AREAS.
 2. SUBGRADE MUST BE APPROVED BY THE CITY ENGINEER.
 3. SEE PROJECT PLANS AND SPECIFICATIONS FOR STREET WIDTH AND STREET SECTION.
 4. TYPICAL SECTION TO BE CONFIRMED WITH SITE SPECIFIC GEOTECHNICAL REPORT.

DRAWN BY: B.D.H.



NOT TO SCALE

UPDATED: 2025

ENGINEERING
DIVISION

PLATE NO: STR-5

TYPICAL STREET SECTION



TAMP ALL TRAIL EDGES AT A 45 DEGREE BEVEL

DRAWN BY: B.D.H.

NOT TO SCALE

UPDATED: 2026

ENGINEERING
DIVISION

PLATE NO: STR-9

BITUMINOUS PATHWAY

NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.

NOT TO SCALE

REV.	BY	DATE	REVISION DESCRIPTION
1	B.D.H.	5/14/26	DESIGN
2	B.D.H.	5/14/26	REVISION
3	B.D.H.	5/14/26	REVISION
4	B.D.H.	5/14/26	REVISION
5	B.D.H.	5/14/26	REVISION
6	B.D.H.	5/14/26	REVISION
7	B.D.H.	5/14/26	REVISION
8	B.D.H.	5/14/26	REVISION
9	B.D.H.	5/14/26	REVISION
10	B.D.H.	5/14/26	REVISION




DESIGNED: JHS
DRAWN: JHS
CHECKED: BJ
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26


HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
DETAILS

SHEET
6
OF
24




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.


NOT TO SCALE		REV.	BY	DATE	REVISION DESCRIPTION	JONES HAUGH SMITH Engineers + Surveyors 415 West North Street Owatonna, MN 56045-4598	DESIGNED: JHS	I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota. John H. Schulte V License No. 44639 Date: 5/14/26	HARVEST HILLS SECOND ADDITION SCHROM CONSTRUCTION OUTLOT A HARVEST HILLS DETAILS	SHEET 8 OF 24
							DRAWN: JHS			
							CHECKED: BJ			
							Date: 5/14/26			
							DWG: 23-259			




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.




NOTE: CITY STANDARD PLATES COPIED HERE FOR CONVENIENCE. PLATES SHOWN VALID AT TIME OF DESIGN. SEE CITY ENGINEER'S OFFICE FOR POSSIBLE REVISIONS.





V-NOTCH WEIR OUTLET STRUCTURE PLAN



POND OUTLET STRUCTURE SECTION

New Sanitary Structure Table			
Structure Name	Structure Details	HEIGHT	SUMP/INV
MH A	RIM = 1021.32 SUMP = 1010.46 INV IN S= 1010.56 INV IN E= 1010.66 INV OUT N= 1010.46	10.86	1010.46
MH B	RIM = 1022.68 SUMP = 1011.58 INV IN S= 1011.68 INV IN E= 1011.58 INV OUT N= 1011.58	11.10	1011.58
MH C	RIM = 1022.72 SUMP = 1012.52 INV OUT W= 1012.52 INV OUT E= 1012.52	10.20	1012.52
MH D	RIM = 1017.26 SUMP = 1005.45 INV IN S= 1007.45 INV IN W= 1006.45 INV IN E= 1006.45 INV OUT N= 1005.45	11.81	1005.45
MH E	RIM = 1022.81 SUMP = 1012.89 INV IN S= 1013.09 INV OUT N= 1012.89	9.92	1012.89
MH F	RIM = 1020.35 SUMP = 1009.05 INV IN E= 1009.15 INV OUT W= 1009.05	11.30	1009.05
MH G	RIM = 1021.99 SUMP = 1003.61 INV IN S= 1003.71 INV OUT N= 1003.61 INV OUT W= 1010.79	18.38	1003.61
MH H	RIM = 1013.20 SUMP = 1004.25 INV IN S= 1004.35 INV OUT N= 1004.25	8.95	1004.25

PHASE 2 UTILITY CONSTRUCTION


W STS Structure Table				
Structure Name	Design	Structure Details	HEIGHT	SUMP/INV
CB 6	4022-48	RIM = 1018.50 SUMP = 1009.78 INV IN NW= 1013.78 INV IN E= 1013.78 INV OUT S= 1013.78	8.72	1009.78
CB 7	4022-48	RIM = 1018.18 SUMP = 1013.90 INV IN W= 1013.93 INV IN N= 1013.90 INV OUT SE= 1013.93	4.28	1013.90
CB 8	SD-1	RIM = 1018.19 SUMP = 1014.10 INV OUT S= 1014.10	4.09	1014.10
CB 9	4022-48	RIM = 1021.63 SUMP = 1014.90 INV IN W= 1015.33 INV IN N= 1014.90 INV OUT E= 1015.18	6.73	1014.90
CB 10	SD-1	RIM = 1021.62 SUMP = 1016.40 INV OUT S= 1016.40	5.22	1016.40
CB 12	SD-1	RIM = 1021.55 SUMP = 1017.57 INV OUT E= 1017.57	3.98	1017.57
CB 13	4022-48	RIM = 1017.64 SUMP = 1014.40 INV IN N= 1014.40 INV IN E= 1014.40 INV OUT W= 1014.40	3.24	1014.40
CB 14	SD-1	RIM = 1017.66 SUMP = 1014.60 INV OUT S= 1014.60	3.06	1014.60
CB 15	SD-1	RIM = 1019.69 SUMP = 1015.10 INV IN N= 1015.69 INV OUT W= 1015.69	4.59	1015.10
CB 16	SD-1	RIM = 1019.67 SUMP = 1015.30 INV OUT S= 1015.80	4.37	1015.30
FES 4	24" FES	RIM = 1015.46 SUMP = 1013.25 INV IN W= 1013.25	2.21	1013.25
MH 5	4020-48	RIM = 1021.40 SUMP = 1013.48 INV IN N= 1013.48 INV OUT E= 1013.48	7.92	1013.48

PHASE 2 UTILITY CONSTRUCTION


E STS Structure Table				
Structure Name	Design	Structure Details	HEIGHT	SUMP/INV
CB 18	SD-1	RIM = 1016.80 SUMP = 1009.30 INV IN E= 1013.40 INV OUT W= 1013.30	7.50	1009.30
CB 19	SD-1	RIM = 1016.79 SUMP = 1012.27 INV OUT W= 1013.60	4.52	1012.27
FES 17	15" FES	RIM = 1009.98 SUMP = ??? INV IN E= 1013.25	1014.01	???

PHASE 2 UTILITY CONSTRUCTION

POND OUTLET Structure Table				
Structure Name	Design	Structure Details	HEIGHT	SUMP/INV
EX MH	Unknown Dia	RIM = 1011.16 SUMP = 1003.80 INV IN S= 1003.80	7.36	1003.80
MH 1	4020-48	RIM = 1017.38 SUMP = 1006.49 INV IN S= 1006.49 INV OUT N= 1006.49	10.89	1006.49
MH 3	4020-48	RIM = 1020.69 SUMP = 1009.12 INV IN E= 1009.12 INV OUT N= 1009.12	11.57	1009.12
OS	SPECIAL - 60"	RIM = 1019.00 SUMP = 1013.25 INV OUT W= 1013.25	5.75	1013.25



SECTION



PLAN

RIP RAP EMERGENCY OVERFLOW

NOT TO SCALE

REV.	BY	DATE	REVISION DESCRIPTION
1	JHS5	4/14/26	ADD POND OUTLET STRUCTURE TABLE



415 West North Street Owatonna, MN 56045-4598

DESIGNED:	JHS5
DRAWN:	JHS5
CHECKED:	BJU
Date:	5/14/26
DWG:	23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION

SCHROM CONSTRUCTION

OUTLOT A HARVEST HILLS

DETAILS

SHEET
15
OF
24

EARTHWORK NOTES:

1. CONTRACTOR TO FURNISH ON SITE GEOTECHNICAL CONSULTING ENGINEER AS REQUIRED.
2. SOIL CORRECTIONS UNDER THE PROPOSED CONCRETE & ASPHALTIC PAVEMENT SHALL INCLUDE, BUT NOT BE LIMITED TO, REMOVAL OF ALL TOPSOIL AND VISIBLY ORGANIC FILL MATERIAL.
3. CONTRACTOR TO FURNISH ON SITE GEOTECHNICAL CONSULTING ENGINEER TO COORDINATE SOIL CORRECTIONS UNDER PAVEMENTS.
4. THE SITE SHALL BE GRADED TO THE CONTOURS SHOWN AND TO PROVIDE THE DRAINAGE PATTERN SHOWN.
5. GRADE ALL AREAS TO DRAIN.
6. THE ENGINEER MAY ORDER ADJUSTMENTS TO THE GRADES SHOWN ON THE PLAN TO ENSURE PROPER OR BETTER DRAINAGE OR UTILITY COVERAGE AS WORK INCIDENTAL TO THE CONTRACT.

TURF ESTABLISHMENT

1. PROVIDE A MINIMUM OF 6" OF TOPSOIL OVER ALL AREAS DESIGNATED TO RECEIVE TURF.
2. STABILIZE ALL OTHER DISTURBED AREAS OF THE SITE NOT SHOWN TO RECEIVE SPECIAL TREATMENT ON THIS PLAN IN ACCORDANCE WITH THE LANDSCAPE PLAN OF IF NOT SHOWN, WITH HYDROSEED MIXTURE AS MNDOT RAPID STABILIZATION METHOD 3 WITH:
SEED MIX 25-131 @ 100 LB/ACRE,
FERTILIZER 22-5-10 @ 300 LBS/ACRE
TYPE 1 HYDRAULIC SOIL STABILIZER

WINTER STABILIZATION


- IN THE EVENT THAT FINAL STABILIZATION OF THE SITE HAS NOT OCCURRED PRIOR TO WINTER CONDITIONS, THE FOLLOWING ACTIVITIES WILL OCCUR:
1. STABILIZE ALL AREAS DESIGNATED TO RECEIVE TURF WITH SODDING OR SEED MIX 22-112 @ 40 LB/ACRE WITH SEED MIX 21-112 (WINTER WHEAT) @ 100 LB/ACRE, AND TYPE 1 MULCH FROZEN TO GROUND WITH WATER
 2. SPOT CHECK AND STABILIZE ALL AREAS ALREADY STABILIZED WITH THE ABOVE

KEYNOTES

- ① CONTOURS SHOWN INCLUDE A 1' HOLD-DOWN FOR STRUCTURE PADS

LEGEND

- 848— EXISTING ELEVATION CONTOUR LINE
—848— PROPOSED ELEVATION CONTOUR LINE



DRAWINGS ON 11x17 SHEETS ARE HALF SCALE

BENCHMARK:

TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62


REV.	BY	DATE	REVISION DESCRIPTION



JONES
HAUGH
SMITH
Engineers + Surveyors


415 West North Street Owatonna, MN 56045-4598

DESIGNED: JHS
DRAWN: JHS
CHECKED: BU
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
OVERALL GRADING PLAN

SHEET
16
OF
24



LEGEND

- 848— EXISTING ELEVATION CONTOUR LINE
—848— PROPOSED ELEVATION CONTOUR LINE



DRAWINGS ON 11x17 SHEETS ARE HALF SCALE

BENCHMARK:

TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION



**JONES
HAUGH
SMITH**
Engineers + Surveyors

415 West North Street Owatonna, MN 56057-4518
507-451-4598


DESIGNED: JHS
DRAWN: JHS
CHECKED: BJ
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
DETAIL GRADING PLAN

SHEET
17
OF
24



LEGEND

- 848 — EXISTING ELEVATION CONTOUR LINE
— 848 — PROPOSED ELEVATION CONTOUR LINE



DRAWINGS ON 11x17 SHEETS ARE HALF SCALE

BENCHMARK:

TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION



415 West North Street Owatonna, MN 56057-4519
507-451-4598


DESIGNED: JHS
DRAWN: JHS
CHECKED: BJU
Date: 5/14/26
DWG: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
OUTLOT A HARVEST HILLS
DETAIL GRADING PLAN

SHEET
18
OF
24



VC=90.00
PVI STA = 1+34.96
PVI ELEV = 1021.95
HP STA = 1+61.96
HP ELEV = 1021.78
M = 0.27
A.D. = 2.36
K = 38.14

LOW POINT EOF
ELEV. 1021.8

STA 2+30.05
1021.50

MH A
2+14.4
0.2' RT
R=1021.32
I=1010.56 (8") S
I=1010.66 (8") E
IO=1010.46 (8") N

CB-12
2+30.1 16.6' RT
TC=1021.55
IO=1017.57 (15") E

PROPOSED CENTERLINE PROFILE

EXISTING CENTERLINE PROFILE

8" MIN BURY

8" DI CL 52 WATER MAIN
WITH PE ENCASEMENT

254 LF 8" PVC SDR 35 SAN @ 0.40%

62 LF 8" PVC SDR 35 SAN @ 1.22%

WATER MAIN CROSSING
WMN FL 1012.5
TOP SAN. 1011.01

CONNECT TO EX WATER MAIN

EX 8" SAN SEWER @ 1.23%

CONNECT TO EX SAN. SEWER
REMOVE 8" PLUG

CONST. 3:1 SLOPE UP TO MATCH

CONST. 20' 8" PVC SDR 35
SANITARY SEWER STUB @
0.40% WITH PLUG
FL1011.76

MH B
4+68.5 0.0' LT
TC=1022.68
I=1011.68 (8") S
IO=1011.58 (8") N

PVS: 0+51.43
PVE: 1020.37

PVS: 4+68.54
PVE: 1022.69

EXISTING CENTERLINE ELEVATION

PROPOSED CENTERLINE ELEVATION


1020.2
1021.3
1021.28
1021.4
1021.76
1020.6
1021.84
1021.5
1021.85
1020.2
1022.10
1021.6
1022.35
1022.9
1022.80
1023.7

1+00
2+00
3+00
4+00
4+81



TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION
-	-	-	-




I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.


John H. Schulte V

License No. 44639 Date: 5/14/26

SHEET
9
OF
24



PROPOSED CENTERLINE PROFILE
EXISTING CENTERLINE PROFILE

CONST. 3:1 SLOPE UP TO MATCH

**PVI: 4+18.07
EL: 1025.98**

**VC=100.00
PVI STA = 1+73.57
PVI ELEV = 1016.09
HP STA=2+23.57
HP ELEV=1017.60
M=0.30
A.D. = 2.38
K = 42.01**

**MH 1
2+25.9 10.7' RT
TC=1017.38
I=1006.49 (12") S
IO=1006.49 (12") N**

**MH 3
3+28.9 4.9' RT
TC=1020.69
I=1009.12 (12") E
IO=1009.12 (12") N**

**MH 5
3+53.6 6.9' RT
TC=1021.40
I=1013.48 (24") N
IO=1013.48 (24") E**

**MH D
3+70.2
0.0' LT
R=1017.26
I=1007.45 (8") S
I=1006.45 (8") W
I=1006.45 (8") E
IO=1005.45 (8") N**

**CB 13
4+07.7 15.5' RT
TC=1017.64
I=1014.40 (15") N
I=1014.40 (15") E
IO=1014.40 (18") W**

**CB 6
3+53.8 37.7' RT
TC=1018.50
I=1013.78 (18") NW
I=1013.78 (18") E
IO=1013.78 (24") S
4' SUMP**

**EX MH
0+86.6 12.0' RT
TC=1011.16
I=1003.80 (12") S**

8" MIN BURY

8" DI CL 52 WATER MAIN WITH PE ENCASEMENT

139 LF 12" RCP STM @ 1.93%

81 LF 8" PVC SDR 35 SAN @ 4.05%

180 LF 8" PVC SDR 35 SAN @ 3.02%

103 LF 12" RCP STM @ 2.55%

100 LF 24" RCP STM @ 0.30%

CONST. 10' 8" PVC SDR 35 SANITARY SEWER STUB @ 0.40% WITH PLUG FL1013.13

CONST. 4 EA 8" 45° BENDS TO MAINTAIN 18" SEPARATION TO STORM SEWER WMN FL 1010.5

CONNECT TO EX STS CORE DRILL & GROUT RING

CONNECT TO EX WATER MAIN

EX 8" SAN SEWER @ 4.05%

CONNECT TO EX SAN. SEWER REMOVE 8" PLUG

NOTE NARROW VERTICAL CROSSING

EXISTING CENTERLINE ELEVATION
PROPOSED CENTERLINE ELEVATION

**0+00 1006.9
1009.4
1011.6
1012.12
1014.0
1014.74
1015.7
1016.83
1018.40
1019.91
1021.1
1024.3
1021.42
1025.6
1022.83
1026.0
1025.98**

0+00 1+00 2+00 3+00 4+00 4+18



BENCHMARK:
TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION
-	-	-	-



415 West North Street Owatonna, MN 507-451-4598

DESIGNED:	JHS5
DRAWN:	JHS5
CHECKED:	SAT
DATE:	5/14/26
FILE NO:	23-259


I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.



John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION SCHROM CONSTRUCTION 2026 CONSTRUCTION FILLMORE STREET PLAN AND PROFILE

SHEET
0
OF
24



The profile view shows the proposed sewer line (solid black line) and existing centerline profile (dashed black line). The sewer line starts at station 0+00 with a 0.90% grade and ends at station 4+33.10 with a -5.96% grade. The existing centerline profile is shown for reference. The sewer line is 8" DI CL 52 WATER MAIN WITH PE ENCASUREMENT. The sewer line is 34 LF 8" PVC SDR 35 SAN @ 0.40% and 184 LF 8" PVC SDR 35 SAN @ 0.29%. The sewer line is 20' 8" PVC SDR 35 SANITARY SEWER STUB @ 0.40% WITH PLUG FL1004.43. The sewer line is 8" SAN SEWER @ 0.40%.

Vertical Curve Data:

- VC=90.00
PVI STA = 1+79.78
PVI ELEV = 1023.70
HP STA=1+50.46
HP ELEV=1023.36
M=0.58
A.D. = 5.14
K = 17.50
- VC=100.00
PVI STA = 3+36.90
PVI ELEV = 1017.02
HP STA=2+86.88
HP ELEV=1019.15
M=0.21
A.D. = 1.71
K = 58.48

Manhole Data:

- MH G
2+16.9 0.5' LT
TC=1021.99
I=1003.71 (8") S
IO=1003.61 (8") N
IO=1010.79 (8") W
- CB 19
3+38.8 16.5' LT
TC=1016.79
IO=1013.60 (15") W
- CB 18
3+38.6 16.7' RT
TC=1016.80
I=1013.40 (15") E
IO=1013.30 (15") W
4' SUMP
- MH H
4+00.8 0.0' RT
TC=1013.20
I=1004.35 (8") S
IO=1004.25 (8") N

Other Notes:

- CONNECT TO EX WATER MAIN
- CONNECT TO EX SAN. SEWER REMOVE 8" PLUG
- EXISTING CENTERLINE ELEVATION
- PROPOSED CENTERLINE ELEVATION
- CONST. 20' 8" PVC SDR 35 SANITARY SEWER STUB @ 0.40% WITH PLUG FL1004.43



TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION
-	-	-	-



415 West North Street Owatonna, MN 507-451-4598

DESIGNED:	JHS5
DRAWN:	JHS5
CHECKED:	SAT
DATE:	5/14/26
FILE NO:	23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.




John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
2026 CONSTRUCTION
GREENFIELD DR E PLAN AND PROFILE

SHEET
21
OF
24


[illegible]

PROPOSED CONSTRUCTION



[illegible]

PROPOSED CONSTRUCTION



BENCHMARK:
TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION
-	-	-	-



415 West North Street Owatonna, MN 507-451-4598

DESIGNED:	JHS5
DRAWN:	JHS5
CHECKED:	SAT
DATE:	5/14/26
FILE NO:	23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.




John H. Schulte V
License No. 44639 Date: 5/14/26


HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
2026 CONSTRUCTION
WHEATLAND DR PLAN AND PROFILE

SHEET
23
OF
24

PRIVATE ROAD



PROPOSED CONSTRUCTION



BENCHMARK:
TNFH SOUTH END OF EXISTING GREENFIELD DR W
ELEVATION 1024.62

REV.	BY	DATE	REVISION DESCRIPTION
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

JONES HAUGH SMITH
Engineers + Surveyors
415 West North Street Owatonna, MN 56045-4598

DESIGNED: JHS
DRAWN: JHS
CHECKED: SAT
DATE: 5/14/26
FILE NO: 23-259

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

John H. Schulte V
License No. 44639 Date: 5/14/26

HARVEST HILLS SECOND ADDITION
SCHROM CONSTRUCTION
2026 CONSTRUCTION
PRIVATE ROAD PLAN AND PROFILE