




Real People. Real Solutions.

## 2020 MILL & OVERLAY PROJECT

#### CITY COUNCIL MEETING FEASIBILITY REPORT 11/05/2019

# 2020 Project Scope

- Mill & Overlay pavement life extended by 15 years
- Concrete Curb and Gutter Spot Repairs
- Sidewalk Spot Repairs
- ADA Upgrades to Existing Pedestrian Ramps
- Intersection Bump-out Analysis
- Bikeways Construction
- Storm Sewer, Sanitary Sewer, & Watermain Adjustments
- Storm Sewer Analysis & Relocations As Necessary



# **Pedestrian Facilities**

- South Side of Third Street (Maple St to Oak St)
- No New Sidewalk Recommended
- Within Scope of Typical Mill & Overlay Project
  Rehabilitation of Existing Infrastructure
- Aligns with Complete Streets Policy due to trees loss and grade challenges
- Doesn't align with Pedestrian/Bike Plan

### **Intersections Bump-out Analysis**

- Bump-outs Increase Pedestrian Safety and Traffic Calming
- Intersection Crosswalks Pedestrian Flow Observation
  Intersections Categorized by Observed Crossing Density
- Highest Crossings Observed Near Specific Destinations
- Limitations Bikeway Conflicts, Delivery Routes, etc.
- Storm Sewer Relocation Necessary to Accomodate
- Bump-outs Recommended for 2 Intersections:
  Third Street & Winona Street (near Central Park)
  Third Street & College Street (near Weitz Center)

# **Bikeway Improvements**


 Bike facilities will be implemented with the Mill & Overlay project

- Locations identified per City of Northfield Pedestrian, Bike, and Trail System Report
- Design follows City of Northfield Complete Streets Policy
- Bikeway additions are only portions of the planned bikeway system
- Considerations on how each option will fit and/or transition to existing and future improvements

### Fourth Street Bikeway Improvements


#### Nevada Street – Prairie Street






# Fourth Street Bikeway

- Nevada Street to Prairie Street
- On-Street Cycle Track
  - Fits in Existing Street Footprint
  - Painted Buffer but No Physical Barrier
  - Eliminates Parking




# **College Street Bikeway Improvements**

First Street – Third Street




- Three Concept Options Evaluated
- No Bikeway Proposed based on Feedback

#### Second Street Bikeway Improvements Washington Street – Oak Street



# Second Street Bikeway


- Washington Street to Oak Street
- On-Street Cycle Track
  - Fits in Existing Street Footprint
  - Painted Buffer but No Physical Barrier
  - Eliminates Parking



# Nevada Street & Eighth Street Bikeway Improvements


First Street – Fourth Street

Linden Street – Water Street



# Nevada Street & Eighth Street Bikeway


• First St to Fourth St & Linden St to Water St




• Fits in Existing Street Footprint

**On-Street Bike Lanes** 

- No Buffer (Commuter Accommodation)
- > Maintains Parking on One Side



#### Heritage Drive Bikeway Improvements Hwy 3 – 500 ft west of Hidden Valley Rd




# Heritage Drive Bikeway

# • TH 3 to 500 ft. west of Hidden Valley Road

#### • On-Street Cycle Track

- Fits in Existing Street Footprint
- Painted Buffer
  but No Physical
  Barrier
- Maintains
  Parking on
  One Side



 Jefferson Road (Heritage Dr to Hidden Valley Rd) will match Existing Bikeway Layout

# **Estimated Project Costs**

ESTIMATED	TOTAL	PROJECT	COSTS
-----------	-------	---------	-------

	ESTIMATED
	COSTS
Street	\$2,881,327
Storm Sewer	\$230,490
Sanitary Sewer	\$27,550
Watermain	\$14,575
Subtotal	\$3,153,942
Art (1%)	\$31,539
Subtotal with Art	\$3,185,481
Contingency (10%)	\$318,548
Construction Total	\$3,504,029
Overhead (20%)	\$700,806
PROJECT COSTS	\$4,204,835

# **Estimated Project Funding**

TOTAL PROJECT FUNDING		
FUNDING SOURCE	ESTIMATED	
	FUNDING	
Bonding	\$2,995,552	
Assessments	\$848,559	
Storm Fund	\$304,984	
Sanitary Fund	\$36,454	
Water Fund	\$19,286	
TOTAL FUNDING	\$4,204,835	

## **Project Process**

• Aug 20, 2019

- Oct 2, 2019
- Oct 15, 2019
- Nov 5, 2019
- Dec 3, 2019
- Jan 8, 2019
- Jan 14, 2020
- Feb 13, 2020
- Feb 18, 2020
- April 14, 2020
- April 2020
- May 5, 2020

- Order Preparation of Feasibility Report/Approve Scope of Services Contract
- Neighborhood Meeting #1
- Council Direction on Bikeway & Sidewalk Concepts
- Accept Feasibility Report & Call for Improvement Hearing & Order Preparation of Plans & Specifications
- Public Improvement Hearing & Order Improvements
- Neighborhood Meeting #2
- Approve Final Plans/Specs & Order Advertisements for Bids
- Bid Opening
- Accept Bids & Award Contract
- Declare Amount to be Assessed/Call for Assessment Hearing
- Property Owner Meetings
- Assessment Hearing/Adopt Assessment Roll
- June to Oct 2020 Construction
  - Accept Improvements & Authorize Final Payment
- June 2021



#### Project Website: https://www.ci.northfield.mn.us/1313/ 2020-Mill-and-Overlay-Project